## **EXISTING TREE LEGEND** ex. tree to remain (typ.) ex. tree to be removed (typ.)

- Information provided on this plan is based on the tree report by project arborist Ray Morneau, 650.964.7664 or ray@rmarborist.com
   Contractor shall contact project arborist for direction on setting up tree protective
- fencing around existing trees to be preserved and protected.

  3. Per tree report by project arborist, the trunks are measured at 54" above soil
- height or as noted.

#### TREE INVENTORY TREES TO BE REMOVED

TREE NO.	COMMON NAME	BOTANICAL NAME	TRUNK DIAMETER (IN.)	TRUNK CIRCUMFERENCE (IN.)	CANOPY RADIUS (FT.)	HEIGHT (FT.)	OVERALL CONDITION
2	Plum	Prunus commonus	3", 3"	26"	10"	38'	49% POOR
3	Plum	Prunus commonus	16" @2"	5 @ 2	g	12	35% POOR
4	Raywood Ash	Freednus oxycerpe "Raywood"	20.9"	66"	9	14'	25% VERY POOR
6	Raywood Ash	Fredinus oxycerpe 'Reywood'	28.3"	89"	9'	20"	25% VERY POOR
6	Raywood Ash	Frednus oxycerpe 'Reywood'	27.2" @ 3"	84"	9	20'	25% VERY POOR
7	Raywood Ash	Frednus oxycarpa 'Raywood'	24.3"	76*	20'	37"	25% VERY POOR
8	Raywood Ash	Frednus oxycerpe 'Reywood'	19.3*	61*	17"	33'	22% VERY POOR
12	Schwedler Maple	Acer platanoides 'Schwedierl'	8.5"	27"	20'	33*	37% POOR
16	Myoporum	Myoporum laetum	17.7" @1'	55 <b>" @</b> 1'	17	25	17% VERY POOR
16	Australian Brush Cherry	Syzyglum paniculatum	5.1"	16"	7	17	35% POOR
17	Jacaranda	Jacaranda mimosifolia	4"	13"	5"	20"	47% POOR
18	Avocado	Persea americana	5", 6"	18", 19"	17"	27	50% POOR
19	Jacaranda	Jacaranda mimosifolia	6"	16"	7	20"	47% POOR
20	Mexican Fan Palm	Washingtonia robusta	20"	63*	8'	30"	67% FAIR
21	Almond	Prunus amygdalus	8", 12", 15"	25", 38", 47"	15"	20"	20% POOR
22	English Walnut	Jugians regia	8.3"	27*	ø	7	00% DEAD
23	Raywood Ash	Frazinus oxycarpa 'Raywood'	11.6"	36"	4	17"	10% VERY POOR
24	Lemon	Citrus limon	5 <b>- 6</b> 8-	16" @ 6"	4	14'	65% FAIR
25	Grapefruit	Citrus x paradisi	7.1*	20"	5"	9	3% VERY POOR

#### TREES TO REMAIN

TREE NO.	COMMON NAME	BOTANICAL NAME	TRUNK DIAMETER (IN.)	TRUNK CIRCUMFERENCE (IN.)	CANOPY RADIUS (FT.)	HEIGHT (FT.)	OVERALL CONDITION
1	Sweet Gum	Liquidambr styraciflua	8.2"	26"	10"	38'	49% POOR
9	Schwedler Maple	Acer platanoides 'Schwedierl'	12.4"	39"	18'	35'	55% FAIR
10	Schwedler Maple	Acer platanoides 'Schwedierl'	34"	108"	22"	35'	42% POOR
11	Schwedler Maple	Acer platanoides 'Schwedieri'	10.9"	35"	21'	33'	34% POOR
13	London Plane Tree	Platanus acerifolia	22.8"	72*	29'	38'	65% FAIR
14	Siberian Elm	Ulmus pumila	27.8" @4"	86" @ 4"	22"	40*	47% POOR

### TREE PROTECTION NOTES:


- 1. Prior to initiating any construction activity in the area, including grading, temporary fencing shall be installed at each alte tree. Fencing shall be located at or beyond the campoy drip line so that 100% of the drip line will be protected by fencing. To reduce soil compaction from equipment, a mulch of 1-2 linch stood wood chips shall be pleaced at a depth of 4 inches where nexecutation is to occur until the vicinity if the trees to be protected.
- 2. The tree protection fence shall be 6' high chain link with immovable posts. The fencing shall form a continuous barrier without entry points around each tree. Any encroachment into the drip line for fencing or construction purposes shall not be permitted.
- 3. Low hanging limbs of saved trees shall be pruned prior to grading, or any equipment mobilization on site. The purpose of this requirement is to avoid tearing limbs by heavy equipment. All limbs to be pruned shall be supervised by the arborist of record for the job.
- 4. This fencing shall serve as a barrier to prevent drip line encroachment of any type of construction activities and equipment. No oils, gas, chemicals, liq wasts, solid wasts, construction machinery or construction materials shall be stored or allowed to stand for any period of time within the drip line of the tree. Further, no one shall enter the fence perimeter for any reason except for the purpose of monitoring the health of the tree. Accidental damage to bark, roct crown, or limbs may increase the potential for future deciline in the health of the tree.
- 5. Contractors and subcontractors shall direct all equipment and personnel to remain outside the fenced area and at all times until the project is complete, and shall instruct employees as to the purpose and importance of fencing.
- 6. A warning sign shall be posted at each tree indicating the purpose of the fencing.
- 7. The arborist of record for the job and or the city arborist shall be responsible for inspection and approval of the fencing prior to any grading operations.
- Fencing must remain in place and shall not be removed until all construction activities are completed. This shall include grading and compaction activities not underground utilities, all construction activities, and any other construction or activity that is scheduled prior to landscape installation.
- 9. Roots of single standing trees often extend up the to three times the distance of the actual drip line and function primarily in the uptake of nutrients and water. The drip line is arbitrarily established as the minimum root area generally required to preserve tree health. As much area around the circumference of the tree should have minimum intrusion to further insure tree survival and health.
- 10. Unauthorized tree removal is subject to in-kind replacement equal to the mature resource lost as determined by the city.
- 11. The contractor is required to water, fertilize and attend to other maintenance needs of existing trees as needed per arborist's recommendations to maintain healthy growth throughout the construction period. Six foot diameter minimum by six to that lie earth berns shall be constructed at the base of sech tree to function as temporary watering bearing during the construction period. Trees shall be watered according to weather and tree requirements.
- 12. Relocation of existing trees (if desired) shall occur under the observation and direction of a certified arborist approved by the city of Mountain View.
  Contact city for additional notes regarding tree location.
- 13. Please consult specifications concerning tree protection and maintenance prepared by project arborist or more information
- 15. All digging within the drip line of trees shall be done by hand.
- 16. Exposed soil after demolition must be covered immediately with a six inch layer of wood chip mulch.

- 17. Incorporate City standard provision 36-03.03 (Protection of Trees during Construction Actvities.)

  a. All edeting heritage trees and designated trees on the \_job site require protection from construction activities with in the drip lines. Temporay chain-link fencing and plastic construction face are acceptable as protective burniers for tree protection purposes. Fencing shall be minimum five feet (5) high. Tree protection shall remain in place until all construction is complete.

  b. No excavation within the tree protection area are allowed unless approved by the City an under the supervision of a licensed arborist. Any filling within the tree protection area shall be done in accordance with a detailed improvement plan approved by the City. No trimming, cutting, or pruning of designated trees can occurs without the approval by the city and supervision of a licensed arborist.

  c. No storage of materials, disposal of paints, solvents or other noxious materials, operation of equipment, parked cars, unnecessary trenching, grading or compaction shall be allowed within the drip line of any trees.



# 田 ALIFORNIA EZ ⋛ H L

ates

Michael Arnone + Associ

337



	a aliv	
DATE	PURPOSE	В
11.7.12		
6.13.13	drc submittal	M
9.9.13	drc resubmittal	M
10.28.13	drc comment resubmittal	M

scale:

1/16" = 1' - 0"& as noted

sheet title:

existing trees

sheet number:

of one

scale: 1" = 30' - 0"

sheet title:

tree growth projection

sheet number:

L - 8 of eight

TYRELLA AVENUE

O

Plan 1

Plan 4

Plan 5

Plan 4

Plan 5

Plan 6

Plan 1

Plan 7

Plan 1

Plan 7

Plan 1

Plan 1

Plan 1

Plan 1

Plan 1

Plan 2

Plan 1

Plan 3

Plan 1

Plan 3

Plan 1

Plan 4

Plan 5

Plan 1

Plan 1

Plan 1

Plan 2

Plan 3

Plan 1

Plan 4

Plan 5

Plan 1

Plan 5

Plan 1

Plan 1

Plan 1

Plan 1

Plan 3

Plan 1

Plan 3

Plan 1

Plan 3

Plan 1

Plan 3

Plan 1

Plan 4

Plan 1

Plan 3

Plan 1


Plan 4

Plan 5


Plan 1

Pla

approximate tree canopy size at time of planting



approximate tree canopy size after 5 year growth period



approximate tree canopy size after 10 year growth period

#### FAIRCHILD DRIVE TREE GROWTH PROJECTIONS Growth at Maturity $H \times W$ 20' x 19' 34' x 30' Acer rubrum 'Red Sunset' 45' x 35' Red Sunset Maple 9-11' x 3-4' 20' x 16' 36' x 26' 45' x 30' Fraxinus americana 'Autumn Purple' 24"-Box 9-11' x 3-4' 14' x 9' 19' x 12' 25' x 15' Moderate 14' x 12' 20' x 22' Olea europea 'Swan Hill' 30' x 30' Fruitless Olive Tree Moderate Platanus x acerifolia 'Columbia' 13-15' x 4-6' Columbia Sycamore 28' x 20' 42' x 35' 40-80' x 30-40'


		T
square footage of existing tree canopy (all trees) *	total square footage of parcel	% of existing tree canopy cover
12,207	43,430 (.99 acre)	28.11%
square footage of existing trees to remain *	total square footage of parcel	% of existing tree canopy cover
6,792	43,430 (.99 acre)	15.63%
square footage of tree canopy @ time of planting		% of tree canopy cover at time of planting
770	43,430 (.99 acre)	1.77%
square footage of tree canopy @ 5 years		% of tree canopy cover at 5 year growth
7567	43,430 (.99 acre)	17.4%
square footage of tree canopy @ 10 years		% of tree canopy cover at 10 year growth
14,722	43,430 (.99 acre)	33.9%
square footage of tree canopy @ maturity		% of tree canopy cover at maturity
17,216	43,430 (.99 acre)	39.6%

\* source: Valley Crest Tree Company Wholesale Catalog specifications (slow = <1' per year; moderate = 1-2' per year; fast = 2-5' per year)

\* \* \* source: 'Sunset Western Garden Book' and 'Plants and Landscapes for Summer-Dry Climates' (EBMUD)

\* see sheet T-1 for approximate diameter of all existing tree canopic

\*\* source: Valley Crest Tree Company Wholesale Catalog specifications



approximate tree canopy size at maturity