

2300 West El Camino Real

2300 West El Camino Real
Mountain View, California



For:
BPR Properties

	<p>Proposed Hotel</p> <hr/> <p>2300 West El Camino Real Mountain View, California</p>	<p>COVER</p> <hr/> <p>April 08, 2020 A0.0</p>
---	---	--

PROJECT DIRECTORY

OWNER

BPR PROPERTIES
953 INDUSTRIAL AVE, SUITE 100
PALO ALTO, CA 94303
ATTN: PERRY PATEL

PHONE: (650) 424-1400
FAX: (650) 328-2924
EMAIL: PPATEL@BPRPROPERTIES.COM

ARCHITECT

ARRIS STUDIO ARCHITECTS
1327 ARCHER STREET, STE 220
SAN LUIS OBISPO, CA 93401
ATTN: THOM JESS
ATTN: ADRIANA COOK

PHONE: (805) 547-2240
FAX: (805) 547-2241
EMAIL: TJESS@ARRIS-STUDIO.COM
EMAIL: ADRIANA@ARRIS-STUDIO.COM

ELECTRICAL

JMPE ELECTRICAL ENGINEERING
156 W ALAMAR AVENUE, SUITE B
SANTA BARBARA, CA 93105
ATTN: JOHN MALONEY

PHONE: (805) 569-9216
EMAIL: MALONEY@JMPE.NET

LANDSCAPE

FIRMA
187 TANK FARM ROAD SUITE 230
SAN LUIS OBISPO, CA 93401
ATTN: LINDSAY CORICA

PHONE: (209) 532-2856
EMAIL: LINDSAY@FIRMACONSULTANTS.COM

CIVIL

ALIQUOT ASSOCIATES
1390 S. MAIN STREET SUITE 310
WALNUT CREEK, CA 94596
ATTN: ROBERT WONG

PHONE: (925) 476-2300
EMAIL: RWONG@ALIQUOT.COM

CONSTRUCTION STAGING

- CONSTRUCTION STAGING AND TRAFFIC CONTROL PLANS REQUIRED AS PART OF THE BUILDING PERMIT SUBMITTAL.
- PARKING FOR CONSTRUCTION MUST BE PROVIDED ON SITE.

SEPARATE PERMIT

SIGNAGE IS NOT PART OF THIS PERMIT AND WILL BE UNDER SEPARATE PERMIT.

AREA INFORMATION

BUILDING AREA	EXISTING	TOTAL PER FLOOR	PROPOSED	TOTAL PER FLOOR	NET INCREASE
BASEMENT				0	
SERVICE			1,885		
FIRST FLOOR		16,211		14,717	-1,494
GUEST	9,344		5,718		
CIRCULATION	3,563		1,948		
HOTEL AMMENITIES	3,107		4,677		
SERVICE	197		2,374		
SECOND FLOOR		12,762		22,005	9,243
GUEST	9,344		18,946		
CIRCULATION	9,418		2,472		
SERVICE			587		
THIRD FLOOR		2,099		19,318	17,219
GUEST	1,312		16,492		
CIRCULATION	787		2,239		
SERVICE			587		
FOURTH FLOOR		0		19,318	19,318
GUEST			16,492		
CIRCULATION			2,239		
SERVICE			587		
TOTAL PER BUILDING		31,072		75,358	44,286

*BASEMENTS DO NOT NEED TO BE INCLUDED IN THE TOTAL ALLOWABLE FLOOR AREA OF A BUILDING PROVIDED THE TOTAL ATREA OF SUCH BASEMENTS DOES NOT EXCEED THE AREA PERMITTED FOR A ONE-STORY ABOVE GRADE PLANE BUILDING

PROJECT INFORMATION

ADDRESS: 2300 WEST EL CAMINO REAL,
MOUNTAIN VIEW, CA
148-36-012

APN:

LOT AREA: 0.97 ACRES (42,138 SF)

ZONING: P(38) EL CAMINO REAL PRECISE PLAN

OCCUPANCY GROUP: R-1 HOTEL OVER S-2 GARAGE

TYPE CONSTRUCTION: TYPE III-A / TYPE 1A

SPRINKLER: YES/ NFPA-13

EXISTING USE: HOTEL

PROPOSED USE: HOTEL

EXISTING GUEST ROOMS: 71

PROPOSED GUEST ROOMS: 153

EXISTING FLOOR AREA: 31,072 S.F.

PROPOSED FLOOR AREA: 75,358 S.F.

EXISTING # OF STORIES: 3 + BASEMENT

PROPOSED # OF STORIES: 4 + BASEMENT

ALLOWED BUILDING HEIGHT (TIER-1): 55'-0"

EXISTING BUILDING HEIGHT: 32'-6"

PROPOSED BUILDING HEIGHT: 52'-6"

EXISTING BUILDING COVERAGE: 17,698 SF

PROPOSED BUILDING COVERAGE: 23,602 SF

ALLOWED FAR (TIER-1): 1.85

EXISTING FAR: 0.81

PROPOSED FAR: 1.79

TOTAL PROPOSED PARKING AREA: 8,661 SF

PARKING COVERED: 6,781 SF

PARKING UNCOVERED: 1,880 SF

ALLOWED MIN. ECR SETBACK: 10 FT

ALLOWED MAX. ECR SETBACK: 15FT

PROPOSED ECR SETBACK: 10 FT

ALLOWED SIDE YARD SETBACK: 15 FT

PROPOSED SIDE YARD SETBACK: 15 FT

ALLOWED REAR YARD SETBACK: 25 FT

PROPOSED REAR YARD SETBACK: 25 FT

ENCROACHMENTS AND EXCEPTIONS:
PER EL CAMINO REAL PRECISE PLAN - ENCROACHMENTS & EXCEPTIONS
SECTION 8: ARCHITECTURAL PROJECTIONS - 2 FT MAX ENCROACHMENT INTO
SETBACKS OTHER THAN EL CAMINO REAL & SIDE STREET SETBACKS.

PARKING INFORMATION

PARKING EXISTING:

BASEMENT LEVEL : 22 STALLS

GROUND LEVEL : 41 STALLS

63 STALLS

NUMBER OF GUEST ROOMS 71 ROOMS

PARKING REQUIRED:

153 GUESTS @ 1 PER 153 STALLS

28 EMPLOYEES @ 0.5 PER 14 STALLS

167 STALLS

PARKING PROPOSED:

BASEMENT: 112 STALLS

GROUND LEVEL: 19 STALLS

131 STALLS *

ACCESSIBLE PARKING:
REQUIRED: 171 REQUIRED STALLS =6 SPACES (INCLUDING 1 VAN)

PROVIDED: =6 SPACES (INCLUDING 1 VAN)

BICYCLE PARKING:
SHORT TERM REQUIRED: 171 X 2%= 4 BIKE SPACES

SHORT TERM PROPOSED: 4 BIKE SPACES

LONG TERM REQUIRED (PER CBGC 5.106.4.1.2): 7 BIKE SPACES

LONG TERM PROPOSED: 8 BIKE SPACES

*SEE TRANSPORTATION DEMAND MANAGEMENT PLAN FOR
PARKING REDUCTION JUSTIFICATION

PROJECT DESCRIPTION

THIS PROJECT CONSISTS OF THE DEMOLITION OF THE EXISTING 71 GUEST ROOM HOTEL AND CONSTRUCTION OF PROPOSED HOTEL. AS PART OF THIS WORK THE NUMBER OF GUEST ROOMS WILL BE INCREASED TO 153.

THE EXISTING BELOW GRADE "CLOSED" PARKING WILL BE EXPANDED AND ADDITIONAL SURFACE PARKING WILL BE ADDED AT THE GRADE LEVEL "OPEN" PARKING GARAGE, THE BELOW GRADE "CLOSED" PARKING WILL BE MECHANICALLY VENTILATED. THE ADDITIONAL PARKING WILL INCREASE THIS NUMBER OF SPACES UP TO 131, A RATIO OF 0.80 PARKING SPACES PER GUEST ROOM.

VALET PARKING WILL BE UTILIZED IN ORDER TO MAKE FULL USE OF THE PROPOSED TANDEM PARKING. THIS EQUALS A 19% REDUCTION IN THE REQUIRED PARKING SPACES. PLEASE SEE THE SUPPLEMENTAL PARKING STUDY FOR REDUCTION JUSTIFICATION.

IN ADDITION, THE EXISTING SWIMMING POOL WILL BE REPLACED BY AN EXPANDED LOBBY, COURTYARD, AND SPA FOR HOTEL GUESTS.

THE CURRENT HOTEL HAS (2) DRIVEWAY ENTRANCES. THESE DRIVEWAY APRONS WILL NEED TO BE KEPT TO ACCOMMODATE TRASH PICK-UP ON THE NORTHWEST END AND THE MAIN HOTEL ENTRY WILL BE TOWARD THE SOUTHEAST END.

PUBLIC SERVICE EASEMENT

WE ARE IN THE PROCESS OF ABANDONMENT OF THE PUBLIC SERVICE EASEMENT, WHICH INCLUDES THE LOT AREA OUTSIDE THE EXISTING BUILDING FOOTPRINT.

THE PUBLIC SERVICE EASEMENT MUST BE VACATED PRIOR TO CONSTRUCTION.

PUBLIC BENEFIT CALCULATION

IN COMPLIANCE WITH THE P-38 (EL CAMINO REAL) PRECISE PLAN, THE APPLICANT IS REQUIRED TO PROVIDE A PUBLIC BENEFIT(S) IN EXCHANGE FOR ADDITIONAL DEVELOPMENT INTENSITY AND TO ADVANCE THE GOALS AND POLICIES OF THE EL CAMINO REAL PRECISE PLAN. THE APPLICANT HAS PROPOSED TO CONTRIBUTE THE PUBLIC BENEFIT FUNDS TO THE CITY AFFORDABLE HOUSING FUND WITH AN ESTIMATED VALUE OF \$443,512.72. FINAL DETAILS OF THE PUBLIC BENEFIT PACKAGE MUST BE REVIEWED AND APPROVED DURING BUILDING PERMIT REVIEW AND COMPLETED PRIOR TO BUILDING PERMIT ISSUANCE.

GUEST ROOM INFORMATION

EXISTING GUEST ROOMS:

FIRST FLOOR: 31 ROOMS

SECOND FLOOR: 36 ROOMS

THIRD FLOOR: 4 ROOMS

FOURTH FLOOR: 0 ROOMS

71 ROOMS

PROPOSED GUEST ROOMS:

FIRST FLOOR: 15 ROOMS

SECOND FLOOR: 50 ROOMS

THIRD FLOOR: 44 ROOMS

FOURTH FLOOR: 44 ROOMS

153 ROOMS

DRAWING INDEX

A 0.0 COVER SHEET

A 0.1 PROJECT DATA

A 0.2 FIRE DEPARTMENT NOTES

A 0.3 AREA DIAGRAMS

A 0.4 SITE PAVING AREA DIAGRAMS

A 0.5 SITE VALET DIAGRAM

A 0.7 OCCUPANCY DIAGRAMS

A 0.8 BUILDING CODE ANALYSIS

A 1.0 EXISTING SITE PLAN / FIRST FLOOR PLAN

A 3.0 PROPOSED SITE PLAN

A 4.0 PROPOSED BASEMENT FLOOR PLAN

A 4.1 PROPOSED FIRST FLOOR PLAN

A 4.2 PROPOSED SECOND FLOOR PLAN

A 4.3 PROPOSED THIRD FLOOR PLAN

A 4.4 PROPOSED FOURTH FLOOR PLAN

A 4.5 PROPOSED ROOF PLAN

A 5.0 RENDERING

A 5.1 RENDERING

A 5.2 RENDERING

A 5.3 RENDERING

A 5.3a RENDERING

A 5.3b RENDERING

A 5.4 RENDERING

A 5.5 RENDERING

A 6.0 PROPOSED ELEVATIONS

A 6.1 PROPOSED ELEVATIONS

A 6.2 PROPOSED ELEVATIONS

A 6.3 PROPOSED ELEVATIONS

A 7.0 SECTION

A 7.1 SECTION

A 7.2 SECTION

A7.3 LINE OF SIGHT STUDY

A 8.0 DETAILS

A 8.1 DETAILS

E 3.1 FIRST FLOOR LIGHTING PLAN

E 3.5 BASEMENT PHOTOMETRIC PLAN

E 3.6 FIRST FLOOR PHOTOMETRIC PLAN

C1.0 GRADING & DRAINAGE PLAN

C1.1 GRADING & DRAINAGE PLAN

C2.0 UTILITY PLAN

C3.0 STORMWATER CONTROL PLAN

C4.0 EROSION CONTROL DETAILS

L.0 CODE COMPLIANCE

L.1 LANDSCAPE SPECIFICATIONS

L.2 IRRIGATION PLAN

L.3 PLANTING PLAN

L.4 LANDSCAPE DETAILS

VICINITY MAP





Proposed
Hotel

2300 West El Camino Real
Mountain View, California

PROJECT
DATA

April 08, 2020

A0.1

FIRE DEPARTMENT NOTES

FIRE SPRINKLER SYSTEM: PROVIDE AN AUTOMATIC FIRE SPRINKLER SYSTEM TO BE MONITORED BY A CENTRAL STATION MONITORING ALARM COMPANY. THIS MONITORING SHALL INCLUDE WATER FLOW INDICATORS AND TAMPER SWITCHES ON ALL CONTROL VALVES. THREE (3) SETS OF SHOP-QUALITY DRAWINGS SHALL BE SUBMITTED FOR REVIEW AND APPROVAL. ALL WORK SHALL CONFORM TO NFPA 13 (2013 EDITION), NFPA 72 (2013 EDITION), AND MOUNTAIN VIEW FIRE DEPARTMENT SPECIFICATIONS. CALL THE BUILDING INSPECTION DIVISION AT (650) 903-6313 FOR A COPY OF SPECIFICATIONS AND SUBMITTAL REQUIREMENTS. (MOUNTAIN VIEW CITY CODE, SECTIONS 14.10.27, 14.10.28, AND CALIFORNIA FIRE CODE, SECTION 903.)

STANDPIPE SYSTEM: PROVIDE A CLASS III STANDPIPE SYSTEM. (MOUNTAIN VIEW CITY CODE, SECTIONS 14.10.29, 14.10.30, 14.10.31, AND 14.10.32 AND CALIFORNIA FIRE CODE, SECTION 905.)

FIRE PROTECTION DURING CONSTRUCTION: EVERY BUILDING FOUR (4) STORIES OR MORE IN HEIGHT SHALL BE PROVIDED WITH NOT LESS THAN ONE (1) STANDPIPE FOR USE DURING CONSTRUCTION. SUCH STANDPIPE(S) SHALL BE INSTALLED WHEN THE PROGRESS OF CONSTRUCTION IS NOT MORE THAN 40' IN HEIGHT ABOVE THE LOWEST LEVEL OF FIRE DEPARTMENT ACCESS. SUCH STANDPIPE(S) SHALL BE PROVIDED WITH FIRE DEPARTMENT HOSE CONNECTIONS AT ACCESSIBLE LOCATIONS ADJACENT TO USABLE STAIRS, AND THE STANDPIPE OUTLETS SHALL BE LOCATED ADJACENT TO SUCH USABLE STAIRS. SUCH STANDPIPE SYSTEMS SHALL BE EXTENDED AS CONSTRUCTION PROGRESSES TO WITHIN ONE FLOOR OF THE HIGHEST POINT OF CONSTRUCTION HAVING SECURED DECKING OR FLOORING. IN EACH FLOOR, THERE SHALL BE PROVIDED A 2.5" VALVE OUTLET FOR FIRE DEPARTMENT USE. (CALIFORNIA FIRE CODE, CHAPTER 33.)

ON-SITE WHARF HYDRANTS: PROVIDE GROUND-LEVEL WET STANDPIPES (WHARF HYDRANTS). ON-SITE WHARF HYDRANTS SHALL BE SO LOCATED AS TO REACH ANY PORTION OF COMBUSTIBLE CONSTRUCTION WITH 150' OF HOSE. INSTALLATION SHALL BE COMPLETE AND THE SYSTEM SHALL BE TESTED PRIOR TO COMBUSTIBLE CONSTRUCTION BEYOND 150' FROM THE PUBLIC RIGHT-OF-WAY. THE WHARF HYDRANT SHALL BE CAPABLE OF PROVIDING A COMBINATION FLOW OF 500 GPM WITH TWO 2.5" OUTLETS FLOWING. THREE (3) COMPLETE SETS OF SHOP-QUALITY DRAWINGS SHALL BE SUBMITTED FOR REVIEW AND APPROVAL. (NFPA 24 (2013 EDITION) AND MOUNTAIN VIEW FIRE DEPARTMENT REQUIREMENTS.)

FIRE EXTINGUISHERS: INSTALL ONE 2-A:10-B:C FIRE EXTINGUISHER FOR EVERY 50'/75' OF TRAVEL OR EVERY 3,000 SQUARE FEET. FIRE EXTINGUISHER LOCATIONS SHALL BE INDICATED ON THE ARCHITECTURAL FLOOR PLANS. (CALIFORNIA CODE OF REGULATIONS, TITLE 19, CHAPTER 3 AND CALIFORNIA FIRE CODE, SECTION 906.)

FIRE EXTINGUISHERS: INSTALL CLASS K FIRE EXTINGUISHERS IN THE COMMERCIAL COOKING EQUIPMENT AREAS. (CALIFORNIA CODE OF REGULATIONS, TITLE 19, CHAPTER 3, AND CALIFORNIA FIRE CODE, SECTION 904.11.5.)

FIRE EXTINGUISHING SYSTEMS: SUBMIT THREE (3) SETS OF SHOP-QUALITY DRAWINGS FOR THE COOKING APPLIANCE FIRE EXTINGUISHING SYSTEM(S). CALL THE BUILDING INSPECTION DIVISION AT (650) 903-6313 FOR A COPY OF SPECIFICATIONS AND SUBMITTAL REQUIREMENTS. (CALIFORNIA FIRE CODE, SECTION 904.2.1.)

AUTOMATIC/MANUAL FIRE ALARM SYSTEM: PROVIDE AN APPROVED AUTOMATIC/MANUAL FIRE ALARM SYSTEM IN ACCORDANCE WITH CALIFORNIA FIRE CODE AND MOUNTAIN VIEW FIRE DEPARTMENT SPECIFICATIONS. THREE (3) COMPLETE SETS OF FIRE ALARM SYSTEM SHOP-QUALITY DRAWINGS SHALL BE SUBMITTED FOR REVIEW AND APPROVAL. PRIOR TO OCCUPANCY, THE SYSTEM SHALL BE FIELD-TESTED, APPROVED, AND IN SERVICE. PROVISIONS SHALL BE MADE FOR MONTHLY TESTING, MAINTENANCE, AND SERVICE. CALL THE BUILDING INSPECTION DIVISION AT (650) 903-6313 FOR A COPY OF SPECIFICATIONS AND SUBMITTAL REQUIREMENTS. (CALIFORNIA FIRE CODE, SECTION 907 AND MOUNTAIN VIEW CITY CODE, SECTION 14.10.33.)

SMOKE ALARMS: ALL RESIDENTIAL OCCUPANCIES SHALL BE PROVIDED WITH CALIFORNIA STATE FIRE MARSHALLISTED SMOKE ALARMS. SMOKE ALARMS SHALL BE INSTALLED IN ACCORDANCE WITH THE CALIFORNIA BUILDING CODE AND THE APPROVED MANUFACTURER'S INSTRUCTIONS. (CALIFORNIA FIRE CODE, SECTION 907.)

LOCKBOX: INSTALL AN APPROVED KEY LOCKBOX PER THE FIRE PROTECTION ENGINEER'S DIRECTIONS. CALL THE BUILDING INSPECTION DIVISION AT (650) 903-6313 FOR INSTRUCTIONS. (CALIFORNIA FIRE CODE, SECTION 506.)

KEYSWITCH: INSTALL AN APPROVED KEY SWITCH PER THE FIRE PROTECTION ENGINEER'S DIRECTIONS. CALL THE BUILDING INSPECTION DIVISION AT (650) 903-6313 FOR INSTRUCTIONS. (CALIFORNIA FIRE CODE, SECTION 506.)
REQUIRED IF THERE IS A GATE FOR UNDERGROUND PARKING GARAGE.

STRETCHER REQUIREMENTS: IN ALL STRUCTURES FOUR (4) OR MORE STORIES IN HEIGHT, AT LEAST ONE ELEVATOR SHALL BE PROVIDED WITH A MINIMUM CLEAR DISTANCE BETWEEN WALLS OR BETWEEN WALLS AND DOOR, EXCLUDING RETURN PANELS, OF NOT LESS THAN 80"X54", AND A MINIMUM DISTANCE FROM WALL TO RETURN PANEL OF NOT LESS THAN 51" WITH A 42" SIDE SLIDE DOOR, UNLESS OTHERWISE DESIGNED TO ACCOMMODATE AN AMBULANCE-TYPE STRETCHER 84"X24" IN THE HORIZONTAL POSITION. (CALIFORNIA BUILDING CODE, SECTION 3002.)

EXIT ILLUMINATION: EXIT PATHS SHALL BE ILLUMINATED ANY TIME THE BUILDING IS OCCUPIED WITH A LIGHT HAVING AN INTENSITY OF NOT LESS THAN ONE FOOTCANDLE AT FLOOR LEVEL. POWER SHALL NORMALLY BE BY THE PREMISES WIRING WITH BATTERY BACKUP. EXIT ILLUMINATION SHALL BE INDICATED ON THE ELECTRICAL PLANS. (CALIFORNIA BUILDING CODE, SECTION 1006.)

EXIT SIGNS: EXIT SIGNS SHALL BE INTERNALLY OR EXTERNALLY ILLUMINATED AND PROVIDED WITH BATTERY BACKUP PER UNIFORM BUILDING CODE CHAPTER 10. EXIT SIGNS SHALL BE POSTED ABOVE EACH REQUIRED EXIT DOORWAY AND WHEREVER OTHERWISE REQUIRED TO CLEARLY INDICATE THE DIRECTION OF EGRESS. (CALIFORNIA BUILDING CODE, SECTION 1011.)

FLOOR-LEVEL EXIT SIGNS: FLOOR-LEVEL EXIT SIGNS SHALL BE PROVIDED IN ALL INTERIOR EXIT CORRIDORS OF GROUP A, E, I, AND GROUP R2.1 OCCUPANCIES AND IN ALL INTERIOR RATED EXIT CORRIDORS SERVING GUEST ROOMS OF HOTELS IN R1 OCCUPANCIES. (CALIFORNIA BUILDING CODE, SECTION 1011.)

EXIT DOORS IN GROUPS A, E, H, AND I OCCUPANCIES: EXIT DOORS SHALL BE PROVIDED WITH APPROVED PANIC HARDWARE. (CALIFORNIA BUILDING CODE, SECTION 1008.1.10.)

GROUP A OCCUPANCIES: BUILDINGS OR PORTIONS OF BUILDINGS USED FOR ASSEMBLY PURPOSES SHALL CONFORM TO ALL REQUIREMENTS OF TITLE 19 AND THE UNIFORM BUILDING CODE. THIS SHALL INCLUDE, BUT IS NOT LIMITED TO: (1) TWO EXITS; (2) FIRE-RETARDANT DRAPES, HANGINGS, CHRISTMAS TREES, OR OTHER SIMILAR DECORATIVE MATERIAL; AND (3) POSTING OF A MAXIMUM OCCUPANT LOAD SIGN. (CALIFORNIA CODE OF REGULATIONS, TITLE 19, SECTIONS 3.08, 3.21, AND 3.30.)

GROUP A, E, I, AND R-1 OCCUPANCIES: DECORATIVE MATERIALS: ALL DRAPES, HANGINGS, CURTAINS, DROPS, AND ALL OTHER DECORATIVE MATERIAL, INCLUDING CHRISTMAS TREES, SHALL BE MADE FROM A NONCOMBUSTIBLE OR FIRERESISTIVE MATERIAL OR MAINTAINED IN A FLAME-RETARDANT CONDITION BY MEANS OF AN APPROVED FLAME-RETARDANT SOLUTION OR PROCESS APPROVED BY THE CALIFORNIA STATE FIRE MARSHAL. (CALIFORNIA CODE OF REGULATIONS, TITLE 19, SECTIONS 3.08 AND 3.21.)

INTERIOR WALL AND CEILING FINISH: INTERIOR FINISHES SHALL HAVE A FLAME-SPREAD RATING IN ACCORDANCE WITH THE CALIFORNIA BUILDING CODE, CHAPTER 8, AND CALIFORNIA CODE OF REGULATIONS, TITLE 19, SECTION 3.21.

UPHOLSTERED SEATING FURNITURE: ALL UPHOLSTERED SEATING FURNITURE INTENDED FOR USE IN NURSING HOMES, BOARD AND CARE FACILITIES, CONVALESCENT HOMES, CHILD DAY-CARE CENTERS, PUBLIC AUDITORIUMS, AND STADIUMS AND PUBLIC ASSEMBLY AREAS IN HOTELS, MOTELS, AND LODGING HOUSES SHALL CONFORM TO STATE OF CALIFORNIA DEPARTMENT OF CONSUMER AFFAIRS, BUREAU OF HOME FURNISHINGS, TECHNICAL BULLETIN 133. (CALIFORNIA BUSINESS AND PROFESSIONS CODE.)

ON-SITE DRAWINGS: SUBMIT TWO (2) 8.5"X11" PLOT PLAN DRAWINGS ACCORDING TO FIRE DEPARTMENT SPECIFICATIONS PRIOR TO FINAL CERTIFICATE OF OCCUPANCY.

EMERGENCY PROCEDURE MAPS: IN HOTELS, MOTELS, AND LODGING HOUSES, EVERY GUEST ROOM AVAILABLE FOR RENTAL SHALL HAVE CLEARLY VISIBLE EMERGENCY PROCEDURES INFORMATION PRINTED ON A FLOOR PLAN REPRESENTATIVE OF THE FLOOR LEVEL AND POSTED ON THE INTERIOR OF EACH ENTRANCE DOOR OR IMMEDIATELY ADJACENT TO SUCH DOOR. THE BOTTOM OF THE INFORMATION SHALL NOT BE LOCATED MORE THAN 4' ABOVE THE FLOOR LEVEL. EMERGENCY PROCEDURES INFORMATION SHALL BE PRINTED WITH A MINIMUM OF 3/16" HIGH NONDECORATIVE LETTERING PROVIDING A SHARP CONTRAST TO THE BACKGROUND. EMERGENCY PROCEDURES INFORMATION SHALL INCLUDE, BUT NOT BE LIMITED TO THE FOLLOWING: (1) LOCATION OF EXITS AND FIRE ALARM INITIATING STATIONS, IF REQUIRED; (2) WHAT THE FIRE ALARM, IF REQUIRED, SOUNDS AND LOOKS LIKE (AUDIBLE AND VISUAL WARNING DEVICES); (3) FIRE DEPARTMENT EMERGENCY TELEPHONE NUMBER, 911; AND (4) THE PROHIBITION OF ELEVATOR USE DURING EMERGENCIES, IF ANY. (CALIFORNIA CODE OF REGULATIONS, TITLE 19, SECTION 3.09.)

STAIRWAY IDENTIFICATION SIGNS: IN BUILDINGS FOUR (4) OR MORE STORIES IN HEIGHT, APPROVED STAIRWAY IDENTIFICATION SIGNS SHALL BE LOCATED AT EACH FLOOR LEVEL IN ALL ENCLOSED STAIRWAYS. THE SIGN SHALL IDENTIFY THE STAIRWAY AND INDICATE WHETHER THERE IS ROOF ACCESS, THE FLOOR LEVEL, AND THE UPPER AND LOWER TERMINUS OF THE STAIRWAY. THE SIGN SHALL BE LOCATED 5' ABOVE THE FLOOR LANDING IN A POSITION WHICH IS READILY VISIBLE WHEN THE DOOR IS IN THE OPEN OR CLOSED POSITION. (CALIFORNIA BUILDING CODE, SECTION 1022.9.)

PREMISES IDENTIFICATION: APPROVED NUMBERS OR ADDRESSES SHALL BE PROVIDED FOR ALL NEW AND EXISTING BUILDINGS IN SUCH A POSITION AS TO BE PLAINLY VISIBLE AND LEGIBLE FROM THE STREET OR ROAD FRONTING THE PROPERTY. ADDRESS SIGNS SHALL BE A MINIMUM OF 6" IN HEIGHT. (MOUNTAIN VIEW CITY CODE, SECTION 14.10.20.)

EMERGENCY ESCAPE OPENING ACCESS: PROVIDE CLEAR SPACE AND LADDER PADS AT GROUND LEVEL FOR EMERGENCY ESCAPE OPENING ACCESS IN R AND I-1 OCCUPANCIES. LADDER PADS SHALL BE ACCESSIBLE BY FIRE CREWS WITH A THREE-SECTION, 12' LONG LADDER. AWNINGS AND WINDOW SHADES SHALL BE DESIGNED TO NOT INTERFERE WITH LADDER ACCESS. (CALIFORNIA BUILDING CODE, SECTION 1029.)

EMERGENCY RESPONDER RADIO COVERAGE: ALL BUILDINGS SHALL HAVE APPROVED RADIO COVERAGE FOR EMERGENCY RESPONDERS WITHIN THE BUILDING. (CALIFORNIA FIRE CODE, SECTION 510.)




Proposed
Hotel

2300 West El Camino Real
Mountain View, California

PROJECT
DATA

April 08, 2020
A0.2

AREA DIAGRAM




THIRD FLOOR AREA DIAGRAM



SECOND FLOOR AREA DIAGRAM



FIRST FLOOR AREA DIAGRAM



FOURTH FLOOR AREA DIAGRAM

BUILDING AREA	
FIRST FLOOR	14,717
SECOND FLOOR	22,005
THIRD FLOOR	19,318
FOURTH FLOOR	19,318
TOTAL BUILDING AREA	75,358
TOTAL LOT AREA	42,138
PROPOSED FAR	1.8

AREA INFORMATION

AREA COLOR LEGEND

 BUILDING AREA
STAIRS & ELEVATORS INCLUDED ON FIRST FLOOR


Arris
STUDIO ARCHITECTS

Proposed
Hotel
2300 West El Camino Real
Mountain View, California

PROJECT
DATA

April 08, 2020

A0.3




TOTAL SITE AREA:	42,138 SF
BUILDING FOOTPRINT:	23,602 SF
23,602 SF / 42,138 SF:	56%
UNCOVERED LOT AREA:	
42,138 SF - 23,602 SF:	18,536 SF
LANDSCAPE AREA:	5,451 SF
5,451 SF / 18,536 SF:	30%
HARDSCAPE AREA:	13,085 SF
13,085 SF / 18,536 SF:	70%
TOTAL PARKING AREA:	8,661 SF
PARKING COVERED:	6,781 SF
PARKING UNCOVERED:	1,880 SF

PAVING AREA INFORMATION

	Proposed Hotel	PROJECT DATA
	2300 West El Camino Real Mountain View, California	April 08, 2020
		A0.4

SITE PAVING AREA DIAGRAM




SITE VALET DIAGRAM




P r o p o s e d H o t e l		SITE VALET DIAGRAM
2300 West El Camino Real Mountain View, California		
		April 08, 2020
		A0.5




SECOND FLOOR OCCUPANCY DIAGRAM (TYPE IIIA)




FIRST FLOOR OCCUPANCY DIAGRAM (TYPE IIIA)



BASEMENT OCCUPANCY DIAGRAM (TYPE 1A)




FOURTH FLOOR OCCUPANCY DIAGRAM (TYPE IIIA)



THIRD FLOOR OCCUPANCY DIAGRAM (TYPE IIIA)

COLOR LEGEND

- A-2 OCCUPANCY
- R-1 OCCUPANCY
- S-2 OCCUPANCY
- B OCCUPANCY



Proposed
Hotel
2300 West El Camino Real
Mountain View, California

OCCUPANCY
DIAGRAMS
April 08, 2020
A0.7

BUILDING CODE ANALYSIS

OVERALL BUILDING STATISTICS

OCCUPANCY GROUPS:	A-2 / B / R-1 / S-2
SEPARATED OCCUPANCIES:	YES
TYPE OF CONSTRUCTION:	TYPE III-A
FIRE SPRINKLERS:	YES (NFPA - 13)
BUILDING HEIGHT ALLOWED:	65 FEET (TABLE 504.3 'S WITH AREA INCREASE') / 50 FEET PER CITY
BUILDING HEIGHT PROPOSED:	50 FEET
NUMBER OF STORIES ALLOWED:	
TYPE III-A:	4 STORIES (TABLE 504.4 'S WITH AREA INCREASE')
STORIES PROPOSED:	4 STORIES + BASEMENT
NUMBER OF GUEST ROOMS:	154
NUMBER OF PARKING SPACES:	131

OVERALL BUILDING AREA BY STORY:

*BASEMENT:	35,785 S.F.	(NOT INCLUDED IN TOTAL)
FIRST STORY:	14,717 S.F.	(FIRST STORY ABOVE PODIUM)
SECOND STORY:	22,005 S.F.	(SECOND STORY ABOVE PODIUM)
THIRD STORY:	19,318 S.F.	(THIRD STORY ABOVE PODIUM)
FOURTH STORY:	19,318 S.F.	(FOURTH STORY ABOVE PODIUM)
TOTAL:	75,358 S.F.	

NOTES:

*SECTION 506.1.3 BASEMENTS.
BASEMENTS NEED NOT BE INCLUDED IN THE TOTAL ALLOWABLE FLOOR AREA OF A BUILDING PROVIDED THE TOTAL AREA OF SUCH BASEMENTS DOES NOT EXCEED THE AREA PERMITTED FOR A ONE-STORY ABOVE GRADE PLANE BUILDING.

**CLOSED PARKING GARAGE:
PER CMC 403.7 - IN CLOSED PARKING GARAGES MECHANICAL VENTILATION MUST BE PROVIDED.
MECHANICAL VENTILATION REQUIRED AT CLOSED GARAGE: (0.75 CFM PER S.F.)
34,066 S.F. x 0.75 CFM = 25,550 CFM REQUIRED
26,000 CFM PROVIDED

HOTEL ROOMS OVER BASEMENT "CLOSED" PARKING GARAGE/PODIUM
TYPE III-A CONSTRUCTION

BUILDING AREA BY STORY & OCCUPANCY:

*BASEMENT (B OCCUPANCY):	1,885 S.F. (NIC IN TOTAL)
*BASEMENT (S-2 OCCUPANCY)	
"CLOSED" PARKING GARAGE**:	34,913 S.F. (NIC IN TOTAL)
FIRST STORY (A-2 OCCUPANCY):	4,677 S.F.
FIRST STORY (B OCCUPANCY):	2,374 S.F.
FIRST STORY (R-1 OCCUPANCY):	6,699 S.F.
FIRST STORY (S-2 OCCUPANCY)	
"OPEN" PARKING GARAGE***:	6,667 S.F.
FIRST STORY (S-2 OCCUPANCY):	967 S.F.
SECOND STORY (R-1 OCCUPANCY):	22,005 S.F.
THIRD STORY (R-1 OCCUPANCY):	19,318 S.F.
FOURTH STORY (R-1 OCCUPANCY):	19,318 S.F.
TOTAL:	75,358 S.F.

ALLOWABLE BUILDING AREA CALCULATION (PER CBC 506.2.4)

Aa = At + (NS x If)
Aa = ALLOWABLE BUILDING AREA PER STORY

A-2 OCCUPANCY
At = PER TABLE 506.2 = SM (WITHOUT HEIGHT INCREASE) = 42,000 S.F.
If = 0
NS = 14,000

Aa = 42,000 S.F. + (14,000 S.F. x 0)
Aa = 42,000 S.F.

TOTAL ALLOWABLE BUILDING AREA = 42,000 S.F. x 1 = 42,000 S.F.

B OCCUPANCY
At = PER TABLE 506.2 = S1 = 114,000 S.F.
If = 0
NS = 28,500

Aa = 114,000 S.F. + (42,000 S.F. x 0)
Aa = 114,000 S.F.

TOTAL ALLOWABLE BUILDING AREA = 114,000 S.F. x 1 = 114,000 S.F.

R-1 OCCUPANCY
At = PER TABLE 506.2 = SM (WITHOUT HEIGHT INCREASE) = 72,000 S.F.
If = 0
NS = 24,000

Aa = 72,000 S.F. + (24,000 S.F. x 0)
Aa = 72,000 S.F.

TOTAL ALLOWABLE BUILDING AREA = 72,000 S.F. x 1 = 72,000 S.F.

S-2 OCCUPANCY
At = PER TABLE 506.2. = S1 = 156,000 S.F.
If = 0
NS = 39,000

Aa = 156,000 S.F. + (39,000 S.F. x 0)
Aa = 156,000 S.F.

TOTAL ALLOWABLE BUILDING AREA = 156,000 S.F. x 1 = 156,000 S.F.

ALLOWABLE BUILDING AREA CALCULATION - PER STORY (PER CBC 508.4.2)

ACTUAL AREA = < 1.00
Aa

MIXED OCCUPANCY - BASEMENT:

B OCCUPANCY
1,885 S.F. / 114,000 S.F. = 0.016

S-2 OCCUPANCY ("CLOSED" PARKING GARAGE)**
34,913 S.F. / 156,000 S.F. = 0.22

TOTAL MIXED OCCUPANCY: 0.016 + 0.22 = 0.25 < 1.00 (OKAY)

MIXED OCCUPANCY - FIRST STORY:

A-2 OCCUPANCY
4,677 S.F. / 42,000 S.F. = 0.11

B OCCUPANCY
2,374 S.F. / 114,000 S.F. = 0.20

R-1 OCCUPANCY
6,699 S.F. / 72,000 S.F. = 0.09

S-2 OCCUPANCY ("OPEN" PARKING GARAGE***)
6,667 S.F. / 156,000 S.F. = 0.04

S-2 OCCUPANCY
967 S.F. / 156,000 S.F. = 0.006

TOTAL MIXED OCCUPANCY: 0.11 + 0.20 + 0.09 + 0.04 + 0.006 = 0.45 < 1.00 (OKAY)

SECOND STORY:

R-1 OCCUPANCY
22,005 S.F. / 72,000 S.F. = 0.31 < 1.00 (OKAY)

THIRD STORY:

R-1 OCCUPANCY
19,318 S.F. / 72,000 S.F. = 0.27 < 1.00 (OKAY)

FOURTH STORY:

R-1 OCCUPANCY
19,318 S.F. / 72,000 S.F. = 0.27 < 1.00 (OKAY)

TOTAL ALLOWABLE BUILDING AREA CALCULATION (PER CBC 506.2.4)

TOTAL AGGREGATE SUM OF RATIOS PER STORY = < 2.00

TOTAL: 0.25 + 0.45 + 0.31 + 0.27 + 0.27 = 1.55 < 2.00 (OKAY)






Proposed
Hotel
2300 West El Camino Real
Mountain View, California

BUILDING CODE
ANALYSIS

April 08, 2020

A0.8






TANDEM PARKING STALLS

THE TANDEM PARKING STALLS WILL NOT BE USED BY GUESTS. THE OVERFLOW PARKING WILL ONLY BE USED BY THE VALET PARKING STAFF. PLEASE SEE SEPARATE VALET PARKING MEMO FOR THE VALET OPERATION, AND TANDEM PARKING.

COLOR LEGEND

 LOBBY/LOUNGE	 SERVICE
 BACK OF HOUSE	 GUEST ROOMS
 REC/AMENITY GYM, SPA DECK	 DINING
 CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR	 LANDSCAPE
	 HARDSCAPE

PROPOSED BASEMENT FLOOR PLAN



Proposed
Hotel

2300 West El Camino Real
Mountain View, California

FLOOR PLANS

April 08, 2020

A4.0



CORTEN STEEL PLANTERS



COLOR LEGEND

<div></div> LOBBY/LOUNGE	<div></div> SERVICE
<div></div> BACK OF HOUSE	<div></div> GUEST ROOMS
<div></div> REC/AMENITY GYM, SPA DECK	<div></div> DINING
<div></div> CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR	<div></div> LANDSCAPE
	<div></div> HARDSCAPE

* HOTEL USES IN REQUIRED GROUND FLOOR COMMERCIAL AREAS MAY INCLUDE LOBBIES, LOUNGES, FITNESS ROOMS OR OTHER USES COMPATIBLE WITH THE PURPOSES AND INTENT OF THESE AREAS. - OTHER LAND USE REQUIREMENTS - #4 HOTEL ACCESSORY STRUCTURES & USES.

PROPOSED FIRST FLOOR PLAN



Proposed
Hotel

2300 West El Camino Real
Mountain View, California

FLOOR PLANS

April 08, 2020

A4.1

PER EL CAMINO REAL PRECISE PLAN -
ENCROACHMENTS AND EXCEPTIONS
SECTION 8: ARCHITECTURAL
PROJECTIONS - 2 FT MAX
ENCROACHMENT INTO SETBACKS
OTHER THAN EL CAMINO REAL AND
SIDE SETBACKS

PER EL CAMINO REAL PRECISE PLAN -
ENCROACHMENTS AND EXCEPTIONS
SECTION 8: ARCHITECTURAL
PROJECTIONS - 2 FT MAX
ENCROACHMENT INTO SETBACKS
OTHER THAN EL CAMINO REAL AND
SIDE SETBACKS


COLOR LEGEND

LOBBY/LOUNGE	SERVICE
BACK OF HOUSE	GUEST ROOMS
REC/AMENITY GYM, SPA DECK	DINING
CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR	LANDSCAPE
	HARDSCAPE

NON-COMMERCIAL
SETBACK - PER
TABLE 10 OF ECR
PRECISE PLAN

COMMERCIAL
SETBACK - PER
TABLE 10 OF ECR
PRECISE PLAN

PROPOSED SECOND FLOOR PLAN





Proposed
Hotel

2300 West El Camino Real
Mountain View, California

FLOOR PLANS

April 08, 2020

A4.2



CORTEN PLANTERS



PER EL CAMINO REAL PRECISE PLAN - ENCROACHMENTS AND EXCEPTIONS SECTION 8: ARCHITECTURAL PROJECTIONS - 2 FT MAX ENCROACHMENT INTO SETBACKS OTHER THAN EL CAMINO REAL AND SIDE SETBACKS

COLOR LEGEND

LOBBY/LOUNGE	SERVICE
BACK OF HOUSE	GUEST ROOMS
REC/AMENITY GYM, SPA DECK	DINING
CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR	LANDSCAPE
	HARDSCAPE

NON-COMMERCIAL SETBACK - PER TABLE 10 OF ECR PRECISE PLAN

COMMERCIAL SETBACK - PER TABLE 10 OF ECR PRECISE PLAN

PROPOSED THIRD FLOOR PLAN




Proposed
Hotel
2300 West El Camino Real
Mountain View, California

FLOOR PLANS

April 08, 2020

A4.3



COLOR LEGEND			
	LOBBY/LOUNGE		SERVICE
	BACK OF HOUSE		GUEST ROOMS
	REC/AMENITY GYM, SPA DECK		DINING
	CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR		LANDSCAPE
			HARDSCAPE

PROPOSED FOURTH FLOOR PLAN

NORTH

1" = 30' @ 11x17

1" = 15' @ 24x36

0

3

6

9

12

15

30

Arris

STUDIO ARCHITECTS

Proposed

Hotel



2300 West El Camino Real

Mountain View, California

FLOOR PLANS

April 08, 2020

A4.4




MECHANICAL SCREEN



Proposed
Hotel
2300 West El Camino Real
Mountain View, California

FLOOR PLANS
April 08, 2020
A4.5

PROPOSED ROOF PLAN





PERSPECTIVE AT EL CAMINO REAL

	Proposed Hotel	PERSPECTIVE
	2300 West El Camino Real Mountain View, California	MARCH 29, 2019
		A5.0



PERSPECTIVE AT EL CAMINO REAL



Proposed
Hotel
2300 West El Camino Real
Mountain View, California

PERSPECTIVE

MARCH 29, 2019

A5.1



PERSPECTIVE AT EL CAMINO REAL - EYE LEVEL



Proposed
Hotel
2300 West El Camino Real
Mountain View, California

PERSPECTIVE

MARCH 29, 2019

A5.2



PERSPECTIVE AT COURTYARD



Proposed
Hotel

2300 West El Camino Real
Mountain View, California


PERSPECTIVE

MARCH 29, 2019

A5.3



PERSPECTIVE AT COURTYARD

	<p>Proposed Hotel</p> <p>2300 West El Camino Real Mountain View, California</p>	<p>PERSPECTIVE</p> <p>MARCH 29, 2019</p> <p>A5.3a</p>
---	---	--




GLASS ENCLOSED
FITNESS CENTER



GLASS RAILING AND PLANTER
AT SPA PERIMETER



VIEW FROM SOUTH



VIEW FROM NORTH

AERIAL VIEWS AT COURTYARD



Proposed
Hotel
2300 West El Camino Real
Mountain View, California

PERSPECTIVE

MARCH 29, 2019

A5.3b



PERSPECTIVE AT LANAI AND HOTEL ENTRY



Proposed
Hotel
2300 West El Camino Real
Mountain View, California

PERSPECTIVE

MARCH 29, 2019

A5.4



PERSPECTIVE AT WALL ART AT NIGHT




Proposed
Hotel

2300 West El Camino Real
Mountain View, California


PERSPECTIVE

MARCH 29, 2019

A5.5



FRONT ELEVATION AT EL CAMINO REAL



Proposed
Hotel

2300 West El Camino Real
Mountain View, California


ELEVATIONS
&
MATERIALS

April 08, 2020

A6.0



EAST ELEVATION



Arris
STUDIO ARCHITECTS

Proposed
Hotel
2300 West El Camino Real
Mountain View, California


ELEVATIONS

April 08, 2020

A6.1




NORTH ELEVATION



	<p>Proposed Hotel</p>	<p>ELEVATIONS</p>
	<p>2300 West El Camino Real Mountain View, California</p>	<p>April 08, 2020</p>
	<p>A6.2</p>	



WEST ELEVATION




Proposed
Hotel

2300 West El Camino Real
Mountain View, California


ELEVATIONS

April 08, 2020


A6.3




1 PER THE EL CAMINO REAL PRECISE PLAN (PG.30 / FIGURE 14.)
- MAXIMUM HEIGHT ADJACENT TO RESIDENTIAL




COLOR LEGEND			
	LOBBY/LOUNGE		SERVICE
	BACK OF HOUSE		GUEST ROOMS
	REC/AMENITY GYM, SPA DECK		DINING
	CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR		LANDSCAPE
			HARDSCAPE



	<p>Proposed Hotel</p>	<p>SECTIONS</p> <p>April 08, 2020</p> <p>A7.0</p>	
	<p>2300 West El Camino Real Mountain View, California</p>		




1 PER THE EL CAMINO REAL PRECISE PLAN (PG.30 / FIGURE 14.)
- MAXIMUM HEIGHT ADJACENT TO RESIDENTIAL



COLOR LEGEND

	LOBBY/LOUNGE		SERVICE
	BACK OF HOUSE		GUEST ROOMS
	REC/AMENITY GYM, SPA DECK		DINING
	CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR		LANDSCAPE
			HARDSCAPE

SECTIONS



Arris
STUDIO ARCHITECTS



Proposed
Hotel

2300 West El Camino Real
Mountain View, California

SECTIONS

April 08, 2020


A7.1



COLOR LEGEND

	LOBBY/LOUNGE		SERVICE
	BACK OF HOUSE		GUEST ROOMS
	REC/AMENITY GYM, SPA DECK		DINING
	CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR		LANDSCAPE
			HARDSCAPE

SECTIONS




Arris
STUDIO ARCHITECTS

Proposed
Hotel
2300 West El Camino Real
Mountain View, California

SECTIONS


April 08, 2020

A7.2




COLOR LEGEND


	LOBBY/LOUNGE		SERVICE
	BACK OF HOUSE		GUEST ROOMS
	REC/AMENITY GYM, SPA DECK		DINING
	CIRCULATION ELEV. LOBBY, CORRIDOR, STAIRS & ELEVATOR		LANDSCAPE
			HARDSCAPE




LINE OF SIGHT STUDY - VIEW FROM THE CORNER OF EL CAMINO REAL & DISTEL DR




	<p>Proposed Hotel</p>	<p>LINE OF SIGHT STUDY</p> <p>April 08, 2020</p> <p>A7.3</p>
	<p>2300 West El Camino Real Mountain View, California</p>	



PLAN



PERSPECTIVE



PROPOSED TRASH ENCLOSURE



Proposed
Hotel

2300 West El Camino Real
Mountain View, California

TRASH
ENCLOSURE

April 08, 2020


A8.0

SMOOTH FINISH
STUCCO
METAL AWNINGS



TRESPA PANEL
RECESSED WINDOWS AND
DOORS
SOLID METAL RAILING W/
HORIZONTAL MEMBERS
WOOD PLANK TRESPA
PANELS
GLASS DOORS

FACADE DETAILS



1	WINDOW JAMB	Window-02
	3" = 1'-0"	


ARCHITECTURAL DETAILS








Proposed
Hotel
2300 West El Camino Real
Mountain View, California

ARCHITECTURAL
DETAILS
April 08, 2020
A8.1

K12 FIRST FLOOR LIGHTING PLAN
1/8" = 1'-0"



Schedule										
Symbol	Label	QTY	Manufacturer	Catalog Number	Description	Lamp	Number Lamps	Lumens per Lamp	LLF	Wattage
	F1	9	Lithonia Lighting		VCPD LED V4 P3 40K 80CRI TSM SRM		1	6174	0.95	43.37
	F2	3	BEGA	33681 K4	33 681 K3	LED 19,8W	1	2093	0.95	23
	F3	10	Lithonia Lighting	LDN6 40/20 LOGAR LSS	6IN LDN, 4000K, 2000LM, 80CRI CLEAR, SEMI-SPECULAR REFLECTOR	LED	1	1970	0.95	22.61
	F4	10	BEGA	33 243 K4	WALL MOUNTED LED 4000K	LED 29,8W	1	4014	0.95	34
	F5	S2	Halo Lighting	69962 -LED LAMP D6L6225-4in JG-BK	Decorative Strand Lighting S2R long 25 E26 sockets 4in drops 3 wire Grounded	120V 60HZ	1	489	0.95	4.91

Statistics						
Description	Symbol	Avg	Max	Min	Max/Min	Avg/Min
EAST WALKWAY	+	2.8 f	6.0 f	0.3 f	20.0 f	9.3 f
FIRST FLOOR DRIVEWAY	+	12.6 f	19.7 f	4.1 f	4.8 f	3.1 f
FIRST FLOOR PARKING	+	5.7 f	5.5 f	2.4 f	2.7 f	2.1 f
FIRST FLOOR PARKING	+	9.7 f	12.5 f	4.8 f	2.6 f	2.0 f
NORTH PARKING	+	2.2 f	13.5 f	0.1 f	135.0 f	22.0 f
PATIO	+	3.9 f	4.5 f	2.8 f	1.6 f	1.4 f
WALKWAY #1	+	5.0 f	6.6 f	3.5 f	1.9 f	1.4 f
WEST SIDEWALK	+	2.8 f	6.5 f	0.3 f	21.7 f	9.3 f

Station Locations						
Sta.	Lat.	Long.	Z	Size	Ts	Generation
1	51	114.28	10.33	1000	500	500
2	51	114.28	10.33	1200	500	96.10
3	51	114.28	10.33	1400	500	96.10
4	51	114.28	10.33	1600	500	96.10
5	51	114.28	10.33	1800	500	96.10
6	51	114.28	10.33	2000	500	96.10
7	51	114.28	10.33	2200	500	96.10
8	51	114.28	10.33	2400	500	96.10
9	51	114.28	10.33	2600	500	96.10
10	51	114.28	10.33	2800	500	96.10
11	51	114.28	10.33	3000	500	96.10
12	51	114.28	10.33	3200	500	96.10
13	51	114.28	10.33	3400	500	96.10
14	51	114.28	10.33	3600	500	96.10
15	51	114.28	10.33	3800	500	96.10
16	51	114.28	10.33	4000	500	96.10
17	51	114.28	10.33	4200	500	96.10
18	51	114.28	10.33	4400	500	96.10
19	51	114.28	10.33	4600	500	96.10
20	51	114.28	10.33	4800	500	96.10
21	51	114.28	10.33	5000	500	96.10
22	51	114.28	10.33	5200	500	96.10
23	51	114.28	10.33	5400	500	96.10
24	51	114.28	10.33	5600	500	96.10
25	51	114.28	10.33	5800	500	96.10
26	51	114.28	10.33	6000	500	96.10
27	51	114.28	10.33	6200	500	96.10
28	51	114.28	10.33	6400	500	96.10
29	51	114.28	10.33	6600	500	96.10
30	51	114.28	10.33	6800	500	96.10
31	51	114.28	10.33	7000	500	96.10
32	51	114.28	10.33	7200	500	96.10
33	51	114.28	10.33	7400	500	96.10
34	51	114.28	10.33	7600	500	96.10
35	51	114.28	10.33	7800	500	96.10
36	51	114.28	10.33	8000	500	96.10
37	51	114.28	10.33	8200	500	96.10
38	51	114.28	10.33	8400	500	96.10
39	51	114.28	10.33	8600	500	96.10
40	51	114.28	10.33	8800	500	96.10
41	51	114.28	10.33	9000	500	96.10
42	51	114.28	10.33	9200	500	96.10
43	51	114.28	10.33	9400	500	96.10
44	51	114.28	10.33	9600	500	96.10
45	51	114.28	10.33	9800	500	96.10
46	51	114.28	10.33	10000	500	96.10
47	51	114.28	10.33	10200	500	96.10
48	51	114.28	10.33	10400	500	96.10
49	51	114.28	10.33	10600	500	96.10
50	51	114.28	10.33	10800	500	96.10
51	51	114.28	10.33	11000	500	96.10
52	51	114.28	10.33	11200	500	96.10
53	51	114.28	10.33	11400	500	96.10
54	51	114.28	10.33	11600	500	96.10
55	51	114.28	10.33	11800	500	96.10
56	51	114.28	10.33	12000	500	96.10
57	51	114.28	10.33	12200	500	96.10
58	51	114.28	10.33	12400	500	96.10
59	51	114.28	10.33	12600	500	96.10
60	51	114.28	10.33	12800	500	96.10
61	51	114.28	10.33	13000	500	96.10
62	51	114.28	10.33	13200	500	96.10
63	51	114.28	10.33	13400	500	96.10
64	51	114.28	10.33	13600	500	96.10
65	51	114.28	10.33	13800	500	96.10
66	51	114.28	10.33	14000	500	96.10
67	51	114.28	10.33	14200	500	96.10
68	51	114.28	10.33	14400	500	96.10
69	51	114.28	10.33	14600	500	96.10
70	51	114.28	10.33	14800	500	96.10
71	51	114.28	10.33	15000	500	96.10
72	51	114.28	10.33	15200	500	96.10
73	51	114.28	10.33	15400	500	96.10
74	51	114.28	10.33	15600	500	96.10
75	51	114.28	10.33	15800	500	96.10
76	51	114.28	10.33	16000	500	96.10
77	51	114.28	10.33	16200	500	96.10
78	51	114.28	10.33	16400	500	96.10
79	51	114.28	10.33	16600	500	96.10
80	51	114.28	10.33	16800	500	96.10
81	51	114.28	10.33	17000	500	96.10
82	51	114.28	10.33	17200	500	96.10
83	51	114.28	10.33	17400	500	96.10
84	51	114.28	10.33	17600	500	96.10
85	51	114.28	10.33	17800	500	96.10
86	51	114.28	10.33	18000	500	96.10
87	51	114.28	10.33	18200	500	96.10
88	51	114.28	10.33	18400	500	96.10
89	51	114.28	10.33	18600	500	96.10
90	51	114.28	10.33	18800	500	96.10
91	51	114.28	10.33	19000	500	96.10
92	51	114.28	10.33	19200	500	96.10
93	51	114.28	10.33	19400	500	96.10
94	51	114.28	10.33	19600	500	96.10
95	51	114.28	10.33	19800	500	96.10
96	51	114.28	10.33	20000	500	96.10



1306 JOHNSON AVENUE
SAN LUIS OBISPO, CA 93401
805/547.2240 805/547.2241

Architect of Record/Consultant



nsultant



BPR PROPERTIES
953 INDUSTRIAL AVENUE
SUITE 100
PALO ALTO, CA 93403


TWO-CORNER AIR VIEW
 HAMPTON INN HOTEL
 2300 WEST EL CAMINO REAL
 FIRST FLOOR PHOTOMETRIC PLAN

[illegible]

A13012
 06/05/2019

E3.6





Client

BPR PROPERTIES
953 INDUSTRIAL AVENUE
SUITE 100
PALO ALTO, CA 93403

**MOUNTAIN VIEW
HAMPTON INN HOTEL**
2300 WEST EL CAMINO REAL
LIGHTING ELEVATIONS

[illegible]

STANDARD GENERAL NOTES

1. THE CONTRACTOR AGREES THAT, IN ACCORDANCE WITH GENERALLY ACCEPTED CONSTRUCTION PRACTICES, THE CONTRACTOR WILL BE REQUIRED SOLE AND COMPLETE RESPONSIBILITY FOR JOB SITE CONDITIONS DURING TO ASSUME THE COURSE OF CONSTRUCTION OF THE PROJECT, INCLUDING SAFETY OF ALL PERSONS AND PROPERTY. THIS REQUIREMENT SHALL BE MADE TO APPLY CONTINUOUSLY AND NOT BE LIMITED TO NORMAL WORKING HOURS. THE CONTRACTOR FURTHER AGREES TO DEFEND, INDEMNIFY AND HOLD OWNER AND ENGINEER HARMLESS FROM ANY AND ALL LIABILITY, REAL OR ALLEGED, IN CONNECTION WITH THE PERFORMANCE OF WORK ON THIS PROJECT, EXEMPTING LIABILITY ARISING FROM THE SOLE NEGLIGENCE OF ENGINEER.
2. EXCAVATIONS SHALL BE ADEQUATELY SHORED, BRACED AND SHEETED SO THAT THE EARTH WILL NOT SLIDE OR SETTLE AND SO THAT ALL EXISTING IMPROVEMENTS OF ANY KIND WILL BE FULLY PROTECTED FROM DAMAGE. ANY DAMAGE RESULTING FROM A LACK OF ADEQUATE SHORING, BRACING AND SHEETING, SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR AND HE SHALL EFFECT NECESSARY REPAIRS OR RECONSTRUCTION AT HIS OWN EXPENSE. WHERE THE EXCAVATION FOR A CONDUIT TRENCH, AND/OR STRUCTURE IS FIVE FEET OR MORE IN DEPTH, THE CONTRACTOR SHALL PROVIDE ADEQUATE SHEETING, SHORING AND BRACING OR EQUIVALENT METHOD, FOR THE PROTECTION OF LIFE, OR LIMB, WHICH SHALL CONFORM TO THE APPLICABLE CONSTRUCTION SAFETY ORDERS OF THE DIVISION OF INDUSTRIAL SAFETY OF THE STATE OF CALIFORNIA, THE CONTRACTOR SHALL ALWAYS COMPLY WITH OSHA REQUIREMENTS.
3. IT IS THE RESPONSIBILITY OF THE CONTRACTOR TO OBTAIN PERMITS NECESSARY TO PERFORM THE WORK SHOWN IN THESE PLANS FROM THE APPROPRIATE AGENCIES.
4. THE CONTRACTOR SHALL TAKE EFFECTIVE ACTION TO PREVENT THE FORMATION OF AN AIRBORNE DUST NUISANCE AND SHALL BE RESPONSIBLE FOR ANY DAMAGE RESULTING FROM HIS FAILURE TO DO SO.
5. THE CONTRACTOR SHALL PROVIDE FOR INGRESS AND EGRESS FOR PRIVATE PROPERTY ADJACENT TO WORK THROUGHOUT THE PERIOD OF CONSTRUCTION.
6. THE CONTRACTOR SHALL PROVIDE ALL LIGHTS, SIGNS, BARRICADES, FLAGGERS OR OTHER DEVICES NECESSARY TO PROVIDE FOR SAFETY.
7. THE CONTRACTOR SHALL POST EMERGENCY TELEPHONE NUMBERS FOR POLICE, FIRE, AMBULANCE, AND THOSE AGENCIES RESPONSIBLE FOR MAINTENANCE OF UTILITIES IN THE VICINITY OF JOB SITE.
8. ANY EXTRA CONSTRUCTION STAKING NECESSITATED SOLELY BY THE CONTRACTOR'S NEGLIGENCE WILL BE CHARGED TO THE CONTRACTOR ON A TIME AND EXPENSES BASIS AND PAID FOR BY THE CONTRACTOR.
9. STATIONING HEREON IS ALONG CONSTRUCTION CENTERLINE UNLESS OTHERWISE SHOWN OR INDICATED.
10. ALL RETURN RADI AND CURB DATA ARE TO FACE OF CURB.
11. WHENEVER BOTTOM OF WALL (BW) ELEVATION IS GIVEN, IT IS FINISH PAVEMENT OR GRADE ELEVATION AT FACE OF WALL.
12. ALL QUANTITIES AND PAY ITEMS ARE AND WILL BE BASED ON HORIZONTAL MEASUREMENTS.
13. LENGTHS OF SANITARY SEWERS AND STORM DRAINS ARE HORIZONTAL DISTANCES FROM CENTER TO CENTER OF STRUCTURES, ROUNDED OFF TO THE NEAREST FOOT.
14. EXISTING UNDERGROUND UTILITIES AND IMPROVEMENTS ARE SHOWN IN THEIR APPROXIMATE LOCATIONS BASED UPON RECORD INFORMATION AVAILABLE TO THE ENGINEER AT THE TIME OF PREPARATION OF THESE PLANS. LOCATIONS MAY NOT HAVE BEEN VERIFIED IN THE FIELD AND NO GUARANTEE IS MADE AS TO THE ACCURACY OR COMPLETENESS OF THE INFORMATION SHOWN. THE CONTRACTOR SHALL NOTIFY UTILITY COMPANIES AT LEAST THREE (3) WORKING DAYS IN ADVANCE OF CONSTRUCTION TO FIELD LOCATE UTILITIES. CALL UNDERGROUND SERVICE ALERT (U.S.A.), AT 800--227--2600. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO DETERMINE THE EXISTENCE AND LOCATION OF THOSE UTILITIES SHOWN ON THESE PLANS OR INDICATED IN THE FIELD BY LOCATING SERVICES. ADDITIONAL COSTS INCURRED AS A RESULT OF CONTRACTOR'S FAILURE TO VERIFY LOCATIONS OF EXISTING UTILITIES PRIOR TO BEGINNING OF CONSTRUCTION IN THEIR VICINITY SHALL BE BORNE BY THE CONTRACTOR AND ASSUMED INCLUDED AND MERGED IN THE CONTRACT UNIT PRICE.
15. THE CONSTRUCTION OF ALL GRAVITY UNDERGROUND LINES (SANITARY SEWERS AND STORM DRAINS) SHALL BEGIN AT THE MOST DOWNSTREAM END, UNLESS OTHERWISE SPECIFICALLY APPROVED BY ALIQUOT ASSOCIATES, INC.
16. ALL EXISTING UTILITIES AND IMPROVEMENTS THAT BECOME DAMAGED DURING CONSTRUCTION SHALL BE COMPLETELY RESTORED TO THE SATISFACTION OF THE CITY ENGINEER OR UTILITY AGENCY REPRESENTATIVE, AT THE CONTRACTOR'S SOLE EXPENSE.
17. ANY RELOCATION OF PUBLIC UTILITIES SHALL BE CONDUCTED IN ACCORDANCE WITH ANY AND ALL REQUIREMENTS OF THE UTILITY COMPANY REPRESENTATIVE INCLUDING FEES, BONDS, PERMITS AND WORKING CONDITIONS, ETC. THIS WORK SHALL BE DONE AT NO EXPENSE TO THE UTILITY COMPANY. THE OWNER SHALL PAY THE COST OF ALL SUCH RELOCATION WORK INCLUDING FEES, BONDS, PERMITS, ETC.
18. IF ARCHEOLOGICAL MATERIALS ARE UNCOVERED DURING GRADING, TRENCHING OR OTHER EXCAVATION, EARTHWORK WITHIN 100 FEET OF THESE MATERIALS SHALL BE STOPPED UNTIL A PROFESSIONAL ARCHEOLOGIST WHO IS CERTIFIED BY THE SOCIETY OF CALIFORNIA ARCHEAEOLOGY (SCA) AND/OR THE SOCIETY OF PROFESSIONAL ARCHEAEOLOGY (SOPA) HAS HAD AN OPPORTUNITY TO EVALUATE THE SIGNIFICANCE OF THE FIND AND SUGGEST APPROPRIATE MITIGATION MEASURES, IF THEY ARE DEEMED NECESSARY.
19. NO ASBESTOS MATERIALS ARE TO BE INSTALLED.
20. THE CONTRACTOR SHALL MEET AND FOLLOW ALL NPDES REQUIREMENTS IN EFFECT AT THE TIME OF CONSTRUCTION.
21. SHOULD IT APPEAR THAT THE WORK TO BE DONE OR ANY MATTER RELATIVE THERETO IS NOT SUFFICIENTLY DETAILED OR EXPLAINED ON THESE PLANS, THE CONTRACTOR SHALL CONTACT ALIQUOT ASSOCIATES, INC. AT (925) 476-2300 FOR SUCH FURTHER EXPLANATIONS AS MAY BE NECESSARY.
22. DURING CONSTRUCTION, THE CONTRACTOR SHALL BE RESPONSIBLE FOR THE PUBLIC SAFETY AND SAFETY OF EXISTING STRUCTURES. THE CONTRACTOR SHALL PROVIDE ADEQUATE BARRICADES, TRAFFIC CONTROLS, SHORING, BRACING AND GUYS IN ACCORDANCE WITH ALL NATIONAL, STATE SPECS AND LOCAL SAFETY ORDINANCES.
23. ALL APPLICABLE REQUIREMENTS OF THE CALIFORNIA CONSTRUCTION AND GENERAL INDUSTRY SAFETY ERRORS, THE OCCUPATIONAL SAFETY AND HEALTH ACT AND THE CONSTRUCTION SAFETY ACT SHALL BE MET.
24. ALL CONSTRUCTION PROCEDURES SHALL CONFORM TO CAL-OSHA STANDARDS. ANY DEVIATION MUST BE APPROVED BY CAL-OSHA PRIOR TO CONSTRUCTION.

CONSTRUCTION NOTES

1. ALL CONSTRUCTION IMPROVEMENTS SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PROVISIONS OF THE CURRENT CITY OF MOUNTAIN VIEW ORDINANCE CODES, CALTRANS STANDARD SPECIFICATIONS, CITY OF MOUNTAIN VIEW STANDARD PLAN. ALL IMPROVEMENTS ARE SUBJECT TO INSPECTION AND APPROVAL BY THE CITY OF MOUNTAIN VIEW.
2. ALL REVISIONS TO THIS PLAN MUST BE REVIEWED BY THE CITY OF MOUNTAIN VIEW PRIOR TO CONSTRUCTION AND SHALL BE ACCURATELY SHOWN ON REVISED PLANS SIGNED BY THE CITY ENGINEER.
3. PRIOR TO PLACING CURB, SIDEWALK, ASPHALT CONCRETE, SUBBASE, OR BASE MATERIAL, ALL UNDERGROUND FACILITIES SHALL BE INSTALLED, BACKFILLED, AND THE PUBLIC WORKS DEPARTMENT'S CONSTRUCTION DIVISION NOTIFIED BY EACH OF THE UTILITY COMPANIES HAVING FACILITIES WITHIN THE WORK AREA THAT THE UTILITY INSTALLATION HAS SATISFACTORILY PASSED ACCEPTANCE TESTS.
4. WHEN CONFORMING TO EXISTING ASPHALT PAVEMENT, THE EXISTING ASPHALT PAVEMENT SHALL BE SAWCUT TO A NEAT LINE AND REMOVED TO AN EXISTING ADEQUATE STRUCTURAL SECTION, OR TO THE ORIGINAL ROAD SECTION. AN EXPLORATORY TRENCH, OR POTHOLES, MAY BE REQUIRED BY THE CITY TO DETERMINE THE LIMITS OF PAVEMENT REMOVAL.
5. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO OCTOBER 15 AND SHALL BE MAINTAINED DAILY UNTIL APRIL 15. THESE MEASURES SHALL CONTROL AND CONTAIN SEDIMENTS AND PROVIDE FOR THE SAFE DISCHARGE OF SLIT-FREE WATERS INTO EXISTING STORM DRAIN FACILITIES. DESIGN OF THESE MEASURES MUST BE APPROVED/UPDATED EACH YEAR BY THE CONTRACTOR PRIOR TO SEPTEMBER 30.
6. A CALIFORNIA DIVISION OF OCCUPATIONAL SAFETY AND HEALTH (CAL OSHA) PERMIT SHALL BE OBTAINED FOR TRENCHES FIVE FEET OR GREATER IN DEPTH. A COPY OF THIS PERMIT SHALL BE SUPPLIED TO THE PUBLIC WORKS DEPARTMENT. AN ADDITIONAL COPY SHALL BE KEPT AT THE JOB SITE AT ALL TIMES.
7. ALL STAKING REQUESTS SHOULD BE DIRECTED TO THE CIVIL ENGINEER. A MINIMUM OF TWO (2) WORKING DAYS PRIOR TO ACTUAL NEED. ANY ADDITIONAL STAKING OR RESTAKING WILL ONLY BE DONE AS DIRECTED AND AUTHORIZED BY THE CLIENT OR HIS AUTHORIZED AGENT. THE CITY ENGINEER HAS THE AUTHORITY TO REQUIRE THE CLIENT OR HIS AUTHORIZED AGENT TO PLACE ADDITIONAL STAKES OR RESTAKES AS HE DEEMS NECESSARY FOR PROPER CONSTRUCTION OR TO AVOID CONFLICTS.
8. THE CONTRACTOR SHALL NOT DESTROY ANY PERMANENT SURVEY POINTS WITHOUT THE CONSENT OF THE CITY ENGINEER. ANY PERMANENT MONUMENTS OR POINTS DESTROYED SHALL BE REPLACED BY A REGISTERED CIVIL ENGINEER OR LICENSED LAND SURVEYOR AT THE CONTRACTOR'S EXPENSE.
9. THE CONTRACTOR SHALL BE HELD RESPONSIBLE FOR ANY FIELD CHANGES MADE WITHOUT WRITTEN AUTHORIZATION FROM THE CITY ENGINEER AND/OR ALIQUOT ASSOCIATES, INC.
10. WITHIN 30 DAYS FROM THE COMPLETION OF WORK, THE CONTRACTOR SHALL PROVIDE A REDLINED COPY OF "AS-BUILT" PLANS FOR RECORD DRAWINGS.
11. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO IMMEDIATELY NOTIFY THE CIVIL ENGINEER AND THE CITY ENGINEER UPON DISCOVERY OF ANY FIELD CONFLICTS.
12. PRIOR TO MOVING ANY MATERIAL TO OR FROM THE SITE, THE CONTRACTOR SHALL OBTAIN APPROVAL FOR HAUL ROUTE FROM THE CITY OF MOUNTAIN VIEW.
13. WHERE ABANDONED UNDERGROUND STRUCTURES ARE ENCOUNTERED IN THE STREET AREAS, REMOVE THE ABANDONED STRUCTURES TO SUFFICIENT DEPTH TO ALLOW UNDERGROUND LINES TO CROSS. THE CITY ENGINEER MAY REQUIRE FURTHER WORK TO BE DONE IF VISUAL INSPECTION INDICATES SO DURING CONSTRUCTION.
14. ALL MANHOLES & VALVE BOXES SHALL BE ADJUSTED TO NEW FINISHED GRADE AFTER FINAL LIFT OF PAVING IS PLACED.

GRADING

1. ALL GRADING OPERATIONS SHALL BE DONE IN ACCORDANCE WITH THE RECOMMENDATIONS AND REQUIREMENTS CONTAINED IN THE GEOTECHNICAL REPORT. SEE GEOTECHNICAL REPORT BY BAGG ENGINEERS DATED FEBRUARY 2015.
2. A REPRESENTATIVE OF THE GEOTECHNICAL ENGINEER SHALL BE ON SITE DURING GRADING AND TRENCH BACKFILL OPERATIONS AND SHALL PERFORM SUCH TESTING AS DEEMED NECESSARY. THE REPRESENTATIVE OF THE GEOTECHNICAL ENGINEER SHALL OBSERVE THE GRADING OPERATION FOR CONDITIONS THAT SHOULD BE MEASURED TO THE CONTRACTOR. THE SOIL ENGINEER OR HIS REPRESENTATIVE SHALL BE NOTIFIED AT LEAST 48 HOURS PRIOR TO START OF THE GRADING OPERATION.
3. THE CONTRACTOR SHALL ESTIMATE THE EARTHWORK QUANTITIES TO HIS OR HER SATISFACTION PRIOR TO THE START OF CONSTRUCTION AND SHALL ARRANGE FOR DISPOSAL OF EXCESS MATERIAL OR ACQUISITION OF IMPORT MATERIAL AS REQUIRED TO COMPLETE THE GRADING AS SHOWN ON THIS PLAN. NO ADDITIONAL COMPENSATION WILL BE MADE FOR ANY EXPORT OR IMPORT REQUIRED.

SANITARY SEWER

1. SANITARY SEWER PIPE, FITTINGS AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE CITY OF MOUNTAIN VIEW CONSTRUCTION SPECIFICATIONS AND DETAILS.
2. CONTRACTOR SHALL EXPOSE THE EXISTING SEWER PIPES AT THE CONNECTION POINTS TO VERIFY THEIR LOCATION AND DEPTHS PRIOR TO CONSTRUCTING ANY NEW SEWER PIPES. CONTRACTOR SHALL NOTIFY THE CIVIL ENGINEER OF MODIFICATIONS AS REQUIRED. CIVIL ENGINEER SHALL BE ALLOWED REASONABLE TIME FOR RESOLUTION OF ANY CONFLICT.
3. CONTRACTOR SHALL OBTAIN AN ENGINEERING PERMIT FOR SEWER CAPPING. IN ACCORDANCE WITH CITY OF MOUNTAIN VIEW POLICY, THE LOWER LATERAL MUST BE CAPPED AT THE POINT AT WHICH IT ENTERS THE MAIN.
4. THE EXISTING BUILDING IS TO BE DEMOLISHED AND THE EXISTING LATERAL IS NOT TO BE RE-USED, THE LATERAL SEWER SHALL BE DUG AND EXPOSED WHERE IT ENTERS THE MAIN.
- A. IF THE LATERAL ENTERS THE MAIN BY MEANS OF A FACTORY MANUFACTURED WYE OR TEE BRANCH, AND IF THE MAIN AND WYE OR TEE BRANCH ARE ALL IN GOOD, UNDAMAGED CONDITION, THE LATERAL SHALL BE DISCONNECTED AND THE BRANCH SHALL BE PLUGGED WITH AN EXPANDABLE NEOPRENE RUBBER PLUG AT THE MAIN. THE BRANCH PLUG SHALL BE ENCLOSED WITH A MINIMUM THICKNESS OF 6 INCHES OF 6 SACK, 3/4" SIZE AGGREGATE, PORTLAND CEMENT CONCRETE. THE WYE BRANCH WITH RUBBER PLUG MUST BE INSPECTED AND APPROVED BY AN ENGINEERING INSPECTOR PRIOR TO ENCLOSURE WITH CONCRETE AND BACKFILL OF THE TRENCH.
- B. IF THE LATERAL ENTERS THE MAIN BY ANY METHOD OTHER THAN BY A FACTORY WYE OR TEE BRANCH, OR IF THE EXISTING MAIN, WYE OR TEE BRANCH IS DAMAGED IN ANY WAY, THE SECTION OF MAIN CONTAINING THE LATERAL ENTRY OPENING SHALL BE REMOVED AND REPLACED WITH A NEW SECTION OF PIPE OF THE SAME DIAMETER AS THE EXISTING MAIN. AN ENGINEERING INSPECTOR MUST INSPECT THE NEW MAIN SECTION BEFORE BACKFILL.
- C. THE ABANDONED LATERAL PIPE SHALL BE FILLED WITH SAND AND JETTED TO PREVENT THE PIPE FROM BECOMING A HOME FOR RODENTS OR OTHER DISEASE VECTORS.

STORM DRAIN


1. STORM DRAIN PIPE SHALL BE AS SPECIFIED ON THE MEP PLANS
2. STORM DRAIN MANHOLES SHALL BE CONSTRUCTED PER MOUNTAIN VIEW CITY STANDARDS.
3. DRAIN PIPES SHALL BE PVC SCH 40 UNLESS OTHERWISE SPECIFIED, AREA DRAINS SHALL BE 4" SPEED--D-BASIN WITH 4" ATRIUM GRATE (OR APPROVED EQUAL BY THE CIVIL ENGINEER).
4. INLETS SHALL BE OLD CASTLE PRECAST TYPE OR AS INDICATED ON THE PLANS.
5. SLOT/TRENCH DRAINS AS SPECIFIED ON THE MEP PLANS.
6. STORMWATER SUMP PUMPS SHALL BE PER MEP PLANS.

WATER SYSTEM

1. ALL WATER PIPES, FITTINGS AND INSTALLATION SHALL BE IN ACCORDANCE WITH THE APPLICABLE REQUIREMENTS OF THE CITY OF MOUNTAIN VIEW CONSTRUCTION SPECIFICATIONS AND DETAILS.
2. EXCAVATIONS MUST BE KEPT DEWATERED AT ALL TIMES SO AS NOT TO ALLOW CONTAMINATED WATER TO ENTER WATER MAINS.
3. THRUST BLOCKS SHALL BE PROVIDED FOR ALL BENDS, TEES, CROSSES, REDUCERS, DEAD ENDS, FIRE HYDRANTS, AND WHERE PIPE CHANGES IN DIRECTIONS OF MORE THAN 11 1/2 DEGREE PER CITY OF MOUNTAIN VIEW SPECIFICATIONS AND DETAILS.
4. AT CROSSING WITH OTHER PIPES, THERE SHALL BE A MINIMUM OF 12" CLEAR DISTANCE BETWEEN WATER MAINS AND OTHER PIPES, UNLESS OTHERWISE NOTED ON THE PLANS.
5. ALL FIRE SERVICE LINES SHALL BE TESTED AND INSPECTED BY THE FIRE DEPARTMENT PRIOR TO ANY BACKFILL.
6. GATE VALVE SHALL CONFORM TO AWWA C509, RESILIENT SEATED TYPE VALVES WITH NONRISING STEMS, AND HAVE "O" RING STUFFING BOXES. STUFFING BOXES SHALL BE BOLTED AND CONSTRUCTED SO AS TO AD VALVE REPAIR. VALVES SHALL OPEN COUNTERCLOCKWISE AND BE FITTED WITH 2-INCH SQUARE OPERATING NUTS. ALL VALVES SHALL BE HYDROSTATICALLY TESTED AND DROPTIGHT AT A PRESSURE OF NOT LESS THAN 350 POUNDS PER SQUARE INCH.

CONCRETE

1. PORTLAND CEMENT SHALL BE TYPE II AND CONFORM TO SECTION 90 OF THE STATE STANDARD SPECIFICATIONS. CONCRETE SHALL BE CLASS B AND HAVE A 28-DAY MINIMUM COMPRESSIVE STRENGTH OF 2500 PSI.
2. AGGREGATE BASE (AB) SHALL BE CLASS 2 CONFORMING TO THE REQUIREMENTS OF SECTION 26 OF THE STATE STANDARD SPECIFICATIONS. THE GRADINGS FOR THE AGGREGATES SHALL BE 3/4" MAXIMUM.
- 1/2" EXPANSION JOINTS SHALL BE CONSTRUCTED AT END OF ALL RETURNS AND AT INTERVAL NOT TO EXCEED 10' AND NO JOINTS SHALL BE CONSTRUCTED IN RETURN.
4. NEW CONCRETE IS TO BE TIED TO THE EXISTING CONCRETE CURB AND SIDEWALK SECTIONS WITH SMOOTH DOWELS. THE DOWELS SHALL BE NO. 4 WITH A MINIMUM LENGTH OF NINE INCHES (9") AND SHALL BE INSTALLED AT EIGHTEEN INCHES (18") ON CENTER ALONG THE EXISTING SECTION. THE DOWELS ARE TO BE INSERTED TO A MINIMUM PENETRATION OF FOUR (4") INTO THE SIDEWALK, CURB, AND GUTTER AND SHALL BE INCORPORATED IN NEW POUR. THE DOWELS ARE TO BE EPOXY GROUTED.
5. THE TOP SURFACE OF THE CURB AND GUTTER SHALL BE FINISHED WITH A STEEL TROWEL TO A SMOOTH FINISH. IMMEDIATELY UPON STRIPPING CURB FORMS AND PRIOR TO BACKFILLING, ALL ROCK POCKETS OR HONEYCOMBS SHALL BE REPAIRED TO THE SATISFACTION OF THE CITY ENGINEER.



W EL CAMINO REAL
TYPICAL CROSS SECTION

Aliquot Associates, Inc.
1390 S. Main St. - Ste. 210
Walnut Creek, CA 94596
Telephone: (925) 476-2300
Fax: (925) 476-2350

Planners
Civil Engineers
Surveyors



GENERAL NOTES
HAMPTON INN HOTEL
2300 W EL CAMINO REAL
SANTA CLARA COUNTY


MOUNTAIN VIEW

Revisions	No.	Date	By	Check	Appr.	Job No.
	1	3/31/2020	MC	MC		217012

Drawing Number:

C0.1

1 OF 7



Aliquot Associates, Inc.
1390 S. Main St., Ste. 210
Walnut Creek, CA 94596
Telephone: (925) 476-2300
Fax: (925) 476-2350

Planners
Civil Engineers
Surveyors

ALIQUOT



CALIFORNIA

GRADING AND DRAINAGE PLAN
HAMPTON INN HOTEL
2300 W EL CAMINO REAL
SANTA CLARA COUNTY

MOUNTAIN VIEW

No.	Revisions
1	

Drawn: MC
Checked: MC
Date: 3/27/2020
Scale: 1"=10'
Drawing: C1.0
Job No: 217012

Drawing Number:
C1.0
2 OF 7

LEGEND

..... DRAINAGE RELEASE ROUTE

DRIVEWAY TRIANGLE OF SAFETY PER CITY STANDARD DETAIL A-22

SLOTS @ WALL GRADE BEAM FOR DRAINAGE RELEASE. LOWERED GRADE @ BEAM

PG&E VAULT

TEL. VAULT

PG&E VAULT



12" WATER

8" SS

6" GAS

NOTES:

1. ALL STORM DRAIN PIPE SHOWN ON THIS SHEET IS HUNG ON THE CEILING OR WALL IN THE BASEMENT
2. ALL CATCH BASINS SHALL BE LABELED WITH "NO DUMPING FLOWS TO BAY"
3. NO BUILDING WILL BE RELEASED FOR OCCUPANCY UNTIL THE OFF-SITE IMPROVEMENTS TO BE CONSTRUCTED TO CITY PUBLIC WORKS STANDARDS AND/OR ACCEPTED FOR MAINTENANCE BY THE CITY ARE COMPLETE AND READY FOR ACCEPTANCE



SEE SOILS REPORT FOR GRADING AND SUBGRADE RECOMMENDATIONS.

SEE MEP PLANS FOR STORM DRAIN PIPE SPECS.

ALL PARKING LEVEL DRAINS TO BE CONNECTED TO THE SANITARY SEWER SYSTEM. SEE P4.00.

W EL CAMINO REAL

Aliquot Associates, Inc.
1390 S. Main St., Ste. 310
Walnut Creek, CA 94596
Telephone: (925) 476-2300
Fax: (925) 476-2350

Planners
Civil Engineers
Surveyors



GRADING AND DRAINAGE PLAN-BELOW GROUND
HAMPTON INN HOTEL
2300 W EL CAMINO REAL
SANTA CLARA COUNTY CALIFORNIA

Revisions	
No.	Description
1	Date: 3/31/2020 Scale: 1"=10' Design: MC Drawn: MC Approved: [Signature] Job No: 217012

Drawing Number:
C1.1
3 OF 7

KEY NOTES

- 1" METER PER CITY STANDARD DETAIL D-1, SHEET C9. METER SHALL BE BADGER RECORDALL DISC SERIES AND METER BOX SHALL BE OLDCASTLE FL12T
- 1" REDUCED PRESSURE BACKFLOW PREVENTER PER CITY STANDARD DETAIL D-05, SHEET C9. FEBCO 825Y OR WILKINS 975XL. 3' MIN. CLR. FROM DOMESTIC BACKFLOW PREVENTER.
- HOT TAP 6" C900 PVC MANIFOLD SERVICE FOR DOMESTIC AND IRRIGATION WATER TO EXISTING WATER MAIN. 36" MIN CLEARANCE BETWEEN 6" HOT-TAP AND 6" HOT-TAP. 30" MINIMUM CLEARANCE BETWEEN 6" HOT-TAP AND PIPE JOINT.
- METER PER CITY STANDARD DETAIL D-2 AND D-3, SHEET C9. 3" METER SHALL BE BADGER TURBO SERIES AND METER BOX SHALL BE OLDCASTLE N52.
- 3" REDUCED PRESSURE BACKFLOW PREVENTER PER CITY STANDARD DETAIL D-05, SHEET C9. WILKINS 375 OR 475. 3' MIN. CLR. FROM DODA AND IRRIGATION BACKFLOW PREVENTER.
- HOT TAP 6" C900 PVC FIRE WATER SERVICE TO EXISTING WATER MAIN PER CITY STANDARD DETAIL D-2, SHEET C9. 36" MIN CLEARANCE BETWEEN 6" HOT-TAP AND 6" HOT-TAP. 30" MINIMUM CLEARANCE BETWEEN 6" HOT-TAP AND PIPE JOINT.
- 6" DOUBLE CHECK DETECTOR ASSEMBLY PER CITY STANDARD DETAIL D-5B, SHEET C9. FEBCO 876 VST OR WILKINS 350 DA OR 450 DA. 3' MIN. CLR. FROM DOMESTIC BACKFLOW PREVENTER.

10 5 0 10 20
SCALE: FEET

- NOTES:
- JOINT TRENCH BY OTHERS
 - FIRE SPRINKLER DESIGNER TO DESIGN AND SIZE FIRE SERVICE AND APPURTENANCES

Aliquot Associates, Inc.
1390 S. Main St., Ste. 310
Walnut Creek, CA 94596
Telephone: (925) 476-2300
Fax: (925) 476-2350

Planners
Civil Engineers
Surveyors



CALIFORNIA

UTILITY PLAN
HAMPTON INN HOTEL
2300 W EL CAMINO REAL
SANTA CLARA COUNTY


MOUNTAIN VIEW

Revisions		No.	Description
		1	
Date	3/27/2020		
Scale	1"=10'		
Design	MC		
Drawn			
Approved			
Job No	217012		

Drawing Number:

C2.0



4 OF 7



DMA #	DMA AREA (SF)	IMP #	TREATMENT AREA REQUIRED	TREATMENT AREA PROVIDED
DMA 1-3	10,245	IMP 1	410	457
DMA 4-8	14,939	IMP 2	598	642
DMA 9	1,121	IMP 3	45	94
DMA 10	6,320	IMP 4	252	252
DMA 11-13	2,478	IMP 5	99	141
DMA 14	504	INTERCEPTOR TREE CREDIT		
DMA 15	70	INTERCEPTOR TREE CREDIT		
DMA 16	467	INTERCEPTOR TREE CREDIT AND DRAINS TO SELF-RETAINING		
DMA 17	56	INTERCEPTOR TREE CREDIT		

TREATMENT AREA REQUIRED=0.04xIMPERVIOUS AREA

TOTAL AREA 42,138
IMPERVIOUS = 35,799



NEW DECIDUOUS INTERCEPTOR TREE MEETING SCVURPPP HANDBOOK GUIDELINES FOR CREDIT FOR DMA 14 AND DMA 15

NEW DECIDUOUS INTERCEPTOR TREES MEETING SCVURPPP HANDBOOK GUIDELINES FOR CREDIT FOR DMA 14 AND DMA 15

EXISTING DECIDUOUS INTERCEPTOR TREE MEETING SCVURPPP HANDBOOK GUIDELINES FOR CREDIT FOR DMA 15 AND DMA 16

EXISTING DECIDUOUS INTERCEPTOR TREE MEETING SCVURPPP HANDBOOK GUIDELINES FOR CREDIT FOR DMA 17

Aliquot Associates, Inc.
1390 S. Main St., Ste. 310
Walnut Creek, CA 94596
Telephone: (925) 476-2300
Fax: (925) 476-2350

Planners
Civil Engineers
Surveyors




CALIFORNIA

STORMWATER CONTROL PLAN
HAMPTON INN HOTEL
2300 W EL CAMINO REAL
SANTA CLARA COUNTY

MOUNTAIN VIEW

Revisions	No.	Date	By	Appr.	Job No.
	1	3/27/2020	MC	MC	217012

Drawing Number:
C3.0
5 OF 7



EROSION CONTROL NOTES:

1. TEMPORARY EROSION CONTROL DEVICES SHOWN ON GRADING PLAN WHICH INTERFERE WITH THE WORK SHALL BE RELOCATED OR MODIFIED WHEN THE INSPECTOR SO DIRECTS AS THE WORK PROGRESSES.
2. EXCEPT AS OTHERWISE DIRECTED BY THE INSPECTOR, ALL DEVICES SHOWN ON THE EROSION CONTROL PLAN SHALL BE IN PLACE AT THE END OF EACH WORKING DAY. ALL EROSION CONTROL FACILITIES MUST BE INSPECTED AND REPAIRED AT THE END OF EACH WORKING DAY.
3. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE CONSTRUCTED AND MAINTAINED IN ACCORDANCE WITH THE CASQA CALIFORNIA STORMWATER BMP HANDBOOK.
4. ALL LOOSE SOIL AND DEBRIS SHALL BE REMOVED FROM THE STREET AREAS UPON STARTING OPERATIONS AND PERIODICALLY THEREAFTER AS DIRECTED BY THE INSPECTOR. THE SITE SHALL BE MAINTAINED SO AS TO MINIMIZE SEDIMENT LADEN RUNOFF TO ANY STORM DRAIN SYSTEM.
5. THE CONTRACTOR SHALL PLACE RUMBLE PLATES AT EACH ROAD ENTRANCE TO THE SITE. ANY MUD THAT IS TRACKED ONTO PAVEMENT SHALL BE REMOVED THE SAME DAY.
6. A CONCRETE WASHOUT IS REQUIRED FOR ALL CONCRETE WORK. THE WASHOUT SHALL CONSIST OF A CONTAINMENT AREA ENCLOSED BY AN EARTHEN DIKE. PLASTIC TARP, COVERING THE CONTAINMENT AREA AND EARTHEN DIKE, SHALL BE STAKED IN AT OUTSIDE EDGE OF EARTHEN DIKE.
7. ADDITIONAL CONTAINMENT METHODS MUST BE PROVIDED FOR ANY WASTE STORAGE AREA, STOCKPILE/MATERIAL STORAGE AREA AND/OR CONSTRUCTION TOILET AREA.
8. STAND-BY CREWS SHALL BE ALERTED BY THE PERMITTEE OR CONTRACTOR FOR EMERGENCY WORK DURING RAINSTORMS.
9. ALL EROSION CONTROL MEASURES WILL BE INSPECTED DAILY AND AFTER EACH STORM. BREACHES IN DIKES AND SWALES WILL BE REPAIRED AT THE CLOSE OF EACH DAY AND WHENEVER RAIN IS FORECAST.
10. TEMPORARY STOCKPILES SHALL BE PROTECTED WITH APPROPRIATE EROSION CONTROL MEASURES.

11. SANDBAGS OR STRAW BALES SHALL BE STOCKPILED ON SITE
12. SANDBAGS REFERRED TO IN THE PRECEDING ITEMS MUST BE FULL. APPROVED SANDBAG FILL MATERIALS ARE DECOMPOSED GRANITE AND/OR GRAVEL.
13. SEWER OR STORM DRAIN TRENCHES THAT ARE OUT THROUGH BASIN DIKES OR BASIN INLET DIKES, SHALL BE PLUGGED WITH SANDBAGS FROM TOP OF PIPE TO TOP OF DIKE. SEWER LINES SHALL FIRST BE ENCASED IN CONCRETE BEFORE SANDBAGS ARE PLACED.
14. ALL OPEN UTILITY TRENCHES SHALL BE BLOCKED AT THE PRESCRIBED INTERVALS FROM THE BOTTOM TO TOP WITH A DOUBLE ROW OF SANDBAGS PRIOR TO BACKFILL. SEWER TRENCHES SHALL BE BLOCKED AT THE PRESCRIBED INTERVALS WITH A DOUBLE ROW OF SANDBAGS EXTENDING DOWNWARD, TWO SANDBAGS FROM THE GRADED SURFACE OF THE STREET. SANDBAGS ARE TO BE PLACED WITH ALTERNATE HEADER AND STRETCHER COURSES. THE INTERVALS PRESCRIBED BETWEEN SANDBAG LOCKING SHALL DEPEND ON THE SLOPE OF THE GROUND SURFACE, BUT NOT EXCEED THE FOLLOWING:

GRADE OF THE STREET	INTERVAL
LESS THAN 2%	AS REQUIRED
2% TO 4%	100 FEET
4% TO 10%	50 FEET
OVER 10%	25 FEET

15. AFTER STORM DRAIN, SANITARY SEWER AND UTILITY TRENCHES ARE BACKFILLED AND COMPACTED, THE SURFACES OVER SUCH TRENCHES SHALL BE MOUNDED SLIGHTLY TO PREVENT CHANNELING OF WATER IN THE TRENCH AREA.
16. SEDIMENT TRAPS SHALL BE CLEANED OUT WHENEVER SEDIMENT REACHES THE SEDIMENT CLEANOUT LEVEL INDICATED ON THE DETAIL ON THIS SHEET. IT IS THE CONTRACTOR'S RESPONSIBILITY TO CLEAN THE DESILTING BASINS AND THE SEDIMENT TRAPS.
17. THIS PLAN MAY NOT COVER ALL THE SITUATIONS THAT ARISE DURING CONSTRUCTION DUE TO UNANTICIPATED FIELD CONDITIONS. VARIATIONS MAY BE MADE TO THESE PLANS IN THE FIELD.
18. EROSION CONTROL STRUCTURES SHALL BE ADJUSTED BY THE CONTRACTOR TO REFLECT ALL CHANGES IN DRAINAGE AS STREETS AND BUILDING PADS ARE BEING INSTALLED.
19. THE CONTRACTOR CAN STORE TEMPORARILY, STOCKPILES AND EROSION CONTROL SUPPLIES, TO HANDLE EMERGENCIES, AND SHALL BE PROTECTED WITH APPROPRIATE EROSION CONTROL MEASURES.
20. THE CONTRACTOR SHALL KEEP AN EMERGENCY PHONE # OF CREW CAPTAIN THAT WILL HANDLE EMERGENCIES.
21. THE CONTRACTOR-ASSIGNED STANDBY CREWS 24 HOURS SEVEN DAYS PER WEEK TO BE CALLED TO WORK DURING EACH RAINSTORM EMERGENCY.
22. THE CONTRACTOR SHALL ASSIGN ONE CREW CAPTAIN RESPONSIBLE FOR DAILY, WEEKLY, MONTHLY INSPECTION DURING WET, AND DRY WEATHER TO BE SURE ALL EROSION CONTROL MEASURES ARE WORKING PROPERLY.
23. DURING SITE WORK CONSTRUCTION, HAZARDOUS MATERIALS SHALL BE CONTAINED IN TRUCKS, WASTE PLACED IN DUMPSTER, AND CONCRETE AND TRUCK WASHING DONE OFFSITE IN APPROVED FACILITIES. VEHICLE AND EQUIPMENT STORAGE AREA LOCATION MAY CHANGE DURING CONSTRUCTION PHASES.

LEGEND

- ~ ~ ~ ~ FIBER ROLL
- INLET PROTECTION
- STABILIZED CONSTRUCTION ENTRANCE




IMPLEMENT ALL EROSION AND SEDIMENT CONTROLS PER CASQA STORMWATER BMP HANDBOOK

IMPLEMENT AS NEEDED AND WHEN APPROPRIATE:

1. SILT FENCES AROUND SITE PERIMETER
2. GRAVEL BAGS SURROUNDING CATCH BASINS
3. FILTER FABRIC OVER CATCH BASINS
4. COVERING OF EXPOSED STOCKPILES
5. CONCRETE WASHOUT AREAS
6. STABILIZED ROCK/GRAVEL DRIVEWAYS AT POINTS OF EGRESS
7. VEGETATION, HYDROSEEDING, OR OTHER SOIL STABILIZATION METHOD

TASKS THAT NEED PERFORMING ROUTINELY:

1. SWEEP STREET
2. CLEAN STORM DRAIN CATCH BASIN



STORAGE AND WASTE MANAGEMENT NOTES:

1. CREATE A CONTAINED AND COVERED AREA ON THE SITE FOR STORAGE OF BAGS OF CEMENT, PAINTS, FLAMMABLES, OILS, FERTILIZERS, PESTICIDES, OR ANY OTHER MATERIALS USED ON THE PROJECT SITE THAT HAVE THE POTENTIAL FOR BEING DISCHARGED TO THE STORM DRAIN SYSTEM BY THE WIND OR IN THE EVENT OF A MATERIAL SPILL. NO HAZARDOUS WASTE MATERIAL SHALL BE STORED ON SITE.
2. GATHER ALL CONSTRUCTION DEBRIS ON A REGULAR BASIS AND PLACE THEM IN A DUMPSTER OR OTHER CONTAINER WHICH IS EMPTIED OR REMOVED ON A WEEKLY BASIS. WHEN APPROPRIATE, USE TARPS ON THE GROUND TO COLLECT FALLEN DEBRIS OR SPLATTERS THAT COULD CONTRIBUTE TO STORMWATER POLLUTION.

Aliquot Associates, Inc.
1390 S. Main St., Ste. 450
Walnut Creek, CA 94596
Telephone: (925) 476-2300
Fax: (925) 476-2350

Planners
Civil Engineers
Surveyors



CALIFORNIA

EROSION CONTROL PLAN
HAMPTON INN HOTEL
2300 W EL CAMINO REAL

SANTA CLARA COUNTY

MOUNTAIN VIEW

Revisions	No.	Date	By	Check	Appr.	Job No.
	1	3/31/2020	MC	MC		217012

Drawing Number:





C4.0

6 OF 7

A large, dense, green evergreen shrub, likely a Japanese Cedar, is planted in front of a light-colored building with a window. The shrub has a conical shape and is very full. The building has a light-colored exterior wall and a window with a white frame. The ground in front of the shrub is covered with brown mulch.



File Name: Fir




Notes:

1. 75% of the Total Parking Area is shaded by Building and Tree Canopy at maturity for Ground Level Parking. Refer to Sheet A0.4 for Covered and Uncovered Parking Statistics at Ground Level. The Covered Parking in the Basement Level was not included in this study.








2. Regarding the overall tree canopy on site, 10.7% of the overall site will be covered by tree canopy at maturity (See Table 2) Therefore, when compared to the existing site conditions the proposed project will add approx. 4,288 SF or 9% tree canopy to the overall site.

	Existing	Time of Planting	5 Year	10 Year	Maturity
Total SF of Parking Covered by Tree Canopy	212 SF	0 SF	19 SF	74 SF	163 SF
Total Percent Canopy Coverage	1%	0%	1%	3%	7%

	Existing	Time of Planting	5 Year	10 Year	Maturity
Total SF of Site Covered by Tree Canopy	212 SF	225 SF	1,800 SF	3,150 SF	4,500 SF
Total Percent Canopy Coverage	1%	1%	4.3%	7.5%	10.7%



- ### TREE CANOPY LEGEND

- | <u>SYMBOL</u> | <u>CLASSIFICATION</u> |
|---|---|
|  | EXISTING TREE RETAINED |
|  | PROPOSED CANOPY TREE |
|  | PROPOSED PALM TREE |
|  | COVERED PARKING LOT AREA - 6,062 SF
(GROUND LEVEL) |
|  | EXPOSED PARKING LOT AREA - 2,298 SF |
|  | PARKING LOT AREA CANOPY COVERAGE |
|  | CANOPY COVERAGE OF ENTIRE SITE |



1306 JOHNSON AVENUE
SAN LUIS OBISPO, CA 93401
805/547.2240 805/547.2241
THOMAS E. JESS ARCHITECT
#C27068
STEPHEN F. RIGOR #C33672

Architect of Record/Consultant



Consultant



BPR PROPERTIES
953 INDUSTRIAL AVENUE
SUITE 100
PALO ALTO, CA 93403


MOUNTAIN VIEW
HAMPTON INN HOTEL
2300 WEST EL CAMINO REAL
LANDSCAPE CANOPY COVERAGE PLAN

[illegible]

Project
FIRMA# 21735

Date 07/15/2020

Sheet



North
N.T.S

	Botanical / Common Name	Retain, Remove or Relocate
1	Quercus Palustris/ Pin Oak	Retain
2	Quercus Palustris/ Pin Oak	Retain
3	Ulmus Parvifolia / Chinese Elm	Remove. (Safety Concern)
4a	Washington Robusta/ Fan Palm	Remove. (Conflict with proposed site development; Relocation unadvised.)
4b	Washington Robusta/ Fan Palm	Remove. (Conflict with proposed site development; Relocation unadvised.)

EXISTING # TREES ON SITE: 26
EXISTING # HERITAGE TREES: 5
NON-HERITAGE TREES: 21

TREES PROPOSED FOR REMOVAL: 24
HERITAGE TREES PLANNED FOR REMOVAL: 3 (See Reasons for Removal Above)

Refer to Arborist Report Dated May 22, 2018 for Suitability for Preservation of Two Fan Palms on Construction Site.

Per arborist report (pg.3), all other trees on the property not labeled 1 through 4 are planned for removal as they are not of a size protected under City ordinance. Approximately 27 new trees are proposed on site as part of schematic landscape plan.



MOUNTAIN VIEW
HAMPTON INN HOTEL
2300 WEST EL CAMINO REAL
HERITAGE TREE MAP

[illegible]

Project	FIRMA #21735
Date	07/15/2020
Sheet	

L-3